

17-32-14W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- BACHUS OIL CO. & AYLWARD DRIG. CO.  
Farm- Stumph-Smith "F" No. 2

SEC. 17 T.32 R. 14W  
C NW

Total Depth. 4703'  
Comm. 10-12-62 Comp. 11-28-62  
Shot or Treated.  
Contractor. Bachus Oil Co.  
Issued. 4-13-63

County Barber  
KANSAS



Elevation. 1927' KR

Production. 1,000 MCF

Figures Indicate Bottom of Formations.

surface sand & rock	50
red bed shale & shells	237
red bed & shale	1066
red bed shale & shells	1533
red bed shale & lime	1850
shale & lime	2110
lime	2435
lime & shale	2559
lime	2650
lime & shale	2800
lime	2982
lime & shale	3100
lime	3205
shale & lime	3255
lime	3307
shale lime & chalk	3491
lime & shale	3853
lime w/chalk	3955
shale & lime	4099
shale & sand	4140
lime	4150
lime & chalk	4290
lime chalk & shale	4388
lime	4629
Mississippi chert	4669
chert & lime	4703
Total Depth	

DST #3 4600-4649' Op 30 min. Rec. 125' GCM  
GTS in 4 min. Ga. 1630 MCF in 5 min., Ga.  
2740 MCF in 20 min., Ga. 2530 MCF in 30 min.  
FP 527-485, BHP 1708/30 - 1613/30.

DST #4 4649-4669' Op 1 hr. Rec. 150' O&GCM  
plus 480' O&GCSW. GTS in 1 hr. FP 126-326,  
BHP 1677/30 - 1666/45.

TOPS: ELECTRIC LOG	
Heebner	3976
Douglas	4009
Lansing	4142
Base Kansas City	4542
Massey	4596
Mississippian	4629

DST #1 3042-3100' Op 45 min. Rec. 58' mud.  
FP 48-56, BHP 702-629.

DST #2 4104-4150' Op 70 min. Rec. 7' mud.  
FP 31-42, BHP 52-42.