

17-32-14W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company- AYLWARD DRILLING CO., ET AL  
Farm-Stumph-Smith "G" No. 1

SEC. 17 T. 32 R. 14W  
C NE SE

Total Depth. 4720'  
Comm. 4-28-62 Comp. 5-15-62  
Shot or Treated.  
Contractor. Aylward Drig. Co.  
Issued. 11-24-62

County Barber

KANSAS



Elevation. 1928' KB

Production. Dry

CASING:

8 5/8" 223' cem w/290 sx.  
5 1/2" 4720' cem w/150 sx.

Figures indicate Bottom of Formations.

sand & red bed	130
red bed & shale	535
shale & shells	1600
lime & shale	2215
lime	2925
lime & shale	3485
lime	3885
lime & shale	3970
lime	4650
cherty lime	4681
chert	4720
Total Depth	

TOPS: LOG

Heebner	3970
Douglas	3996
Brown Lime	4102
Stalnaker	4124
Lansing	4136
Base Kansas City	4546
Massy	4599
Mississippian	4627

DST 4126-39', op 1 hr, GTS 4 min, gauge 180,000, 14 min-171,700, 25 min-161,000 stabilized. IBHP 1487# - FBHP 1445#, FP 73#-189#, Rec. 540' Fl., 180' Mdy SW, 360' SW.

DST 4574-4620', op 65 min, Rec. 50' gassy mud. IBHP 164#/30 min, FBHP 416#/30 min, FP 31#-31#.

DST 4629-50', op 2 hrs, 25 min. GTS 4 min, stabilized 235,000 Rec. 60' gassy mud IBHP 1745# - FBHP 1692#, FP 47#-47#.

DST 4650-81', op 1 hr, 5 min. Rec. 70' Sl. O&GCM. 1020' Sl. O&GCSW, IBHP 1703# FBHP 1642#, FP 202#-485#.