

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


28-32-14W

Company. PETROLEUM, INC.
Farm. Jacobs "F" No. 1

SEC. 28 T. 32 R. 14W
Approx. NE NE SE

Total Depth. 4808'
Comm. 4-12-58 Comp. 4-17-58
Shot or Treated.
Contractor. Garvey Drlg. Co.
Issued. 9-6-58

County Barber
KANSAS



CASING:
Attempt to run 13 3/8" surface casing:
Lost 1 joint in hole, could not recover.

Elevation. 1948' DF

Production. Abandon & Plug

Figures indicate Bottom of Formations.

surface clay & sand 30
red bed & sand 315
red bed 930
dry drill (no samples) 1050
Total Depth (Lost Hole)

Skid rig 200' N & 175 E to drill second test.
Production: 75 BOPD Elevation 1929' DF
Location: App. C W/2 NE NE SE
Comm. 4-18-58 Comp. 5-5-58
Casing record: 13 3/8" 320' w/300 sx.
8 5/8" 1040' w/125 sx.
5 1/2" 4803' w/125 sx.

surface clay & sand 100
red bed & gyp w/sand strks 330
shells & red bed 435
red bed & shells 790
dry drill - no returns 1045
red bed & gyp 1190
shale & red rock 1400
shale 1570
shale & lime 2190
lime & shale 2515
shale & lime w/sand 2595
shale & lime 2715
shale & shells 2815
shale & lime 3005
shale 3210
shale & lime 3650
shale & broken lime 3855
shale & lime 4050
shale 4170
lime & shale 4255
lime 4650
lime & chert 4677
shale, lime & sand 4715
lime 4722
lime & chert 4745

chert	4760
chert & lime	4775
lime	4808
Total Depth	
TOPS: SCOUT	
Elgin Sh.	3877
Heebner	4021
Douglas Sh	4079
Lansing	4197
Base Kansas City	4614
Marmaton	4625
Mississippi Chert	4732
Mississippi Lime	4767