

IMPORTANT
Kans. Geo. Survey request
samples on this well.

15-007-2002 7-0001

KANSAS DRILLERS LOG

API No. 15 — 007 — 20,027-A
County Number

Operator
Texas Oil & Gas Corp.

Address
300-200 W. Douglas Wichita, Kansas 67202

Well No. #1 Lease Name
Cline-Mills "A" (OWWO)

Footage Location
1980 feet from (N) (S) line 1980 feet from (E) (W) line

Principal Contractor Geologist
H-30 Drlg., Inc. High Plains Consulting, Ltd.

Spud Date Total Depth P.B.T.D.
11-04-77 4324' 4195'


Date Completed Oil Purchaser
N/A N/A

S. 30 T. 32 R. 14 E
W

Loc. NW SE

County Barber

640 Acres
N



Locate well correctly

Elev.: Gr. 1947'

DF 1952' KB 1955'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{4}$ "	8-5/8"		278'			
Production		4 $\frac{1}{2}$ "	10.5#	4285'	50/50 Pozmix	225	18% NaCl

LINER RECORD

Top, ft. Bottom, ft. Sacks cement
N/A N/A N/A

PERFORATION RECORD

Shots per ft. Size & type Depth interval
4 Deep Penet. 4226-28'
4 " 4144-50'

TUBING RECORD

Size Setting depth Packer set at
2-3/8" ± 4100' N/A

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
2,000 gal. acid; 150# acid flakes; 9000# sand; 8,250 gal. wtr	4226-28' & 4144-50'

INITIAL PRODUCTION

Date of first production Producing method (flowing, pumping, gas lift, etc.)
N/A N/A

RATE OF PRODUCTION PER 24 HOURS Oil Gas Water Gas-oil ratio
N/A bbls. N/A MCF N/A bbls. N/A CFPB

Disposition of gas (vented, used on lease or sold) Producing interval (s)
N/A N/A

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Texas Oil & Gas Corp.

Well No.

1

Lease Name

Cline-Mills "A" (OWWO)

Operations Suspended

S 30 T 32S R 14 E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Chase Group	2310	-355		
Ft. Riley	2496	-541		
Council Grove Group	2670	-715		
Wabaunsee Group	3185	-1230		
Tarkio	3333	-1378		
Heebner Shale	4069	-2114		
Douglas Sd	4143	-2188		
Lansing	4250	-2295		
TD	4324	-2369		
PBTD	4195	-2240		
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received

HAROLD A. BROWN

Signature

District Geologist

Title

May 19, 1978

Date

15-007-20027

Geological Survey

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

WICHITA BRANCH

COMPANY **Texas Oil And Gas Company**


SEC. 30 T. 32S R. 14W
LOC. NW SE

FARM **Cline-Mills "A" NO. 1 (OWWO)**

TOTAL DEPTH **5,177' by prior operator**
COMM. **November 3, 1977** COMP. **November 6, 1977**
SHOT OR TREATED
CONTRACTOR **H-30, Inc.**
ISSUED **November 18, 1977**

COUNTY **Barber**

KANSAS



CASING

20	10	
15	8 - 5/8"	287' cemented w/225 sxs cement ELEVATION 1,355' K.B.
12	6	(by prior operator)
13	5	4-1/2" 4,285' cemented w/225 sxs cement PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Washed down to **4,324'**

Rotary Total Depth **5,177'**

I hereby certify the above and foregoing to be
a true and correct log of the above described
well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } ss:

Suscribed and sworn to before me a Notary Public
in and for said county and state this 17th day of
November, 1977



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:
June 30, 1978