

SCOUT TICKET

COUNTY Clark STATE Kansas DATE 3/6/55

COMPANY Shamrock

FARM J. E. Stephens "I" NO. 1

SEC. 14 TWP. 32 RGE. 21 ELEV. 2024 DF
2017 GF

Location in Sec. 2400 FS					
Fr. N.	2570'	Fr. S.			
Fr. E.	1390'	Fr. W.			
Lines of Section					

PERFORATIONS	GAS PAYS		CASING RECORD
	Hollenberg	Lam 4469	13 7/8" 557(550)
	Herington	Mar 4870	10 3/4"
	Padock	Mar 5230	8 3/8"
	Krider	Schl 5248	7" 5248(300)
	Odel	Cim 1040	6"
Mar 5224	Winfield	Well 1595	5 1/2"
" 5234	Gage	Well 2394	TD
	U. Ft. Riley	Her 2456	PB
	L. Ft. Riley	Kri 2498	Nat
		PMM 3322	Acid
		Missouri 4116	AA
		Lam-NC 4476	DEL
		Mar 4860	Rock
		Cher 5081	

Contractor Company

3/11/55 TTD 580: Reaming

MAR 17 1955
MAR 24 1955
MAR 31 1955
APR 7 1955

φ 2836
φ 3923
φ 4884
DST 5222-36 1 3/4 hrs gas in 8 1/2 min
176 MCF - 248 MCF rec 120' GCM
ul sli show @ top FP 19-25"
BHP 1770 # (30) HH 2595-2560"
φ 5236-49 Rec 11' 9"
1' sd crs grain fairly fit
ul sat str good cut, odor
& Fluor
4" sd Med-Crs ul good pore
sat. Lt str & Fluor
1' sd as above ul good str
& Fluor & pore
3' sd Med-Crs as above
ul sat str good Fluor
& Pore Asphaltic odor

5229
2022
3205

3' sd Mod-Crs ul sat str
Good Fluor Asphaltic
odor

DST 5231-49 15 min gas in 1 min
hvy spray mud & Dist in 5 min
14,000 MCF (max) through 4" Flow Line
Rec 15' Free oil FDP 1650-1625#
BHP 1795# (30) H/H 2620-2595#

RTD 5249 SGL 5248

WOC

APR 1 1955

Rate CO to 5248

(56) 5232-46

Ran 2 3/8 Tby to 5237

Gauged 24600 MCF to 25600 MCF
through Annulus Gas mat w/ oil

FDP 110# FTP 110#

SITP 1510# (30) SICP 1575# (30)

APR 21 1955

WOT

APR 28 1955

Bomb

AOF (Bottom Hole) 51000 MCF

SI BHP 1825.7#

SE WHP 1570#

MAY 5 1955

Produced @ rate 42 BOPD 1/2 @ 3/4" choke
GPA 153.1°

MAY 1 1955
MAY 19 1955

⌘