

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

2-32-15 W


Company. NATIONAL COOPERATIVE REFINERY ASS'N.
Farm. Skinner No. 1

SEC. 2 T. 32 R. 15W
NW NW NE

Total Depth. 5220'
Comm. 4-7-57 Comp. 5-1-57
Shot or Treated.
Contractor. Aylward Drilg. Co.
Issued. 5-16-59

County Barber

KANSAS



Elevation. 1927' KB

Production. 26,000,000 CFG

CASING:

8 5/8" 235' cen w/175 sx.
5 1/2" 5219' cen w/275 sx.

Figures indicate Bottom of Formations.

shale & red rock sanc	70	DST 4203-23' op 1 hr, mod. bl. thruout. rec. 20' Dr. mud., IBHP 220#/20", FBHP 75#/20" FP 0-0#.
GYP	130	
red rock	235	
red bed & gyp shells & red bed	350	DST 4247-63', op 1 hr, mod. bl. thruout, rec. 50' O, spkd MSW, 60' SW, IBHP 1655#/20", FBHP 1490#/20", FP 15#-65#.
red bed & shells shells & red bed	950	
shale & red bed	1007	
salt & shale	1373	
shale & lime	1580	DST 4388-4400' op 1 hr, mod. bl. thruout, rec. 45' GC&O spkd M. IBHP 1100#/20", FBHP 0#/20". FP 0-0#.
lime & shale	1670	
lime	1780	
lime & shale	2025	
lime	2630	DST 4482-93', op 1 hr, good bl. thruout, rec. 50' Sl. O&GCM & 30' Sl. O&GCM. IBHP 1615#/20" FBHP 895#/20" FP 20-35#.
lime & shale	3325	
shale & lime	3374	
lime & shale	3555	
shale & lime	3642	DST 4572-83', op 40", wk. bl./15", died, flushed after 30", Sl. after 40", rec. 8' mud. IBHP 0#/20", FBHP 840#/20", FP 0#-0#.
shale & sand	3765	
shale & lime	3838	
lime & shale	3940	
shale & lime	4080	DST 4704-32', op 1 hr, wk. bl. thruout, rec. 60' gas & 7' mud. IBHP 340#/20", FBHP 120#/20", FP 20-20#.
sand	4091	
lime & shale	4245	
lime	4653	
lime & shale	4685	DST 4742-66', op 1 hr, gas in 4", 2,930 MCFG 10", 4,830/12", 5,020/15", 5,210/25", 5,400/35", 5,590/1 hr, IBHP 1675#/20", FBHP 1625#/20", FP 975#-1055#.
lime	4837	
lime & shale	4965	
lime	5105	
sandy lime	5117	
lime & shale	5175	DST 4766-86', op 1 hr, Gas/2", gauged 4,160/10", 4,640/20", 4,640/1 hr, IBHP 1670#, FBHP 1630#. FP 735#-755#.
lime	5219 RTD	
lime	5220	
Total Depth		

TOPS:

Heebner	3975
Toronto	4006
Douglas	4032
Douglas Sand	4080
Lansing	4155
Base Kansas City	4563
Massey	4630
Mississippi	4700
Kinderhook	4781
Viola	4966
Simpson Sand	5088
Simpson Shale	5122
Arbuckle	5182

DST 4075-91', op 1 hr, good bl. thruout, rec. 75' sl. O&GCM & 240' SW. IBHP 1503/20" FBHP 1318#/20", FP 30-275#.

DST 4203-52' op 1 hr, str. bl. Gas to surf. in 13", not enough to gauge. rec. 105' Hvy. O&GCM, 200' Gsy. Oil & 270' MSW. IBHP 1612#/20", FBHP 1618#/20". FP 132-374#.