


2-32-15 W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

NATIONAL COOPERATIVE REF'RY ASS'N. & SEC. 2 T. 32 R. 15W
Company- AYLWARD DRILLING CO. SE NW SE
Farm- Skinner "C" No. 1

Total Depth. 4991
Comm. 5-8-57 Comp. 5-30-57
Shot or Treated.
Contractor. Aylward Drilling Co.
Issued. 7-13-57

County Barber
KANSAS



Elevation. 1914 DF

CASING:
8 5/8 @ 210' w/ 150 sx cmt.

Production. Dry

Figures indicate Bottom of Formations.

red rock	125	DST #3: 4191-4205, open 1 hr SI 20
shale	280	min. rec. 30' HGC&SOCM, Fp 0-100#
red bed & shale	1070	IBHP 0#, FBHP 220#
red bed & rock	1110	
salt	1155	DST #4: 4207-30, open 1 hr SI 20
red bed & red rock	1290	min. rec. 635' SGCSW, FP 165-370#
red rock & shale	1480	IBHP 1650#, FBHP 1460#
lime & shale	2195	
lime	2242	DST #5: 4355-75, open 1 hr SI 20
lime & shale	2345	min. rec. 2280' gas, 95' O&GCM, FP
lime	2450	40-65#, IBHP 1640#, FBHP 860#
lime & shale	2865	
shale w/ some lime	2975	DST #6: 4817-41, mis-run plugged
lime & shale	3065	tool.
lime w/ shale	3220	
lime & shale	3735	DST #7: 4817-41, open 1 hr. SI 20
sand	3750	min. rec. 13' mud, FP 0-0# BHP 0#
lime w/ shale	3800	
sandy lime & shale	3928	DST #8: 4840-70, open 1 hr SI 20
lime & shale	4030	min. rec. 19' mud FP 14-28#, IBHP
sand & lime	4150	42#, FBHP 42#
mostly lime	4181	
lime	4480	
lime & shale	4522	
lime w/ shale	4575	
lime & shale	4630	
lime	4774	
lime & shale	4816	
lime	4870	
chert & shale	4903	
lime & chert	4934	
lime	4955	
shale & sand	4973	
sand	4991	
Total Depth		

TOPS:

Heebner	3951
Toronto	3987
Douglas	4008
Douglas sand	4039
Lansing	4128
Base KC	4532
Massey	4598
Viola	4826
Simpson shale	4944
Simpson sand	4946

DST #1: 4041-62, open 1 hr. SI 20 min.
rec. 300' gas, 65' SGCM, FP 30-45#
IBHP no good, FBHP 170#

DST #2: 4112-29, open 1 hr SI 20 min.
rec. 7' mud, FP 33-33#, IBHP 47#, FBHP
40#