

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


2-32-15W

Company- NATIONAL COOPERATIVE REFG. ASS'N.
Farm- NCRA Skinner "C" No. 2

SEC. 2 T. 32 R. 15W
NW NW SW

Total Depth. 4935'
Comm. 6-24-57 Comp. 7-12-57
Shot or Treated.
Contractor. Aylward Drlg. Co.
Issued. 10-5-57

County Barber KANSAS



CASING:
8 5/8" 203' w/150 sx cem.
5 1/2" 4933' w/100 sx cem.

Elevation. 1971' DF

Production. 130 BOPD

Figures indicate Bottom of Formations.

red bed	60	DST 4890-4915 Open 1 hr. Shut in
gyp	105	20 min. Rec. 600' free oil &
red bed-shale	880	120' HOCM. IBHP 1700#, FBHP
shale-shells	1868	1665#/20 min. FP 55-175#. Gas
shale-lime shelves	2175	to surf. in 14 min. Not enough
lime	2245	to gauge.
lime w/shale	2375	
lime-shale	2580	
lime w/shale	2670	
shale-lime	3605	
lime	3660	
lime-shale	3751	
sand	3850	
sdv lime	3860	
shale-lime	3956	
shale-sdv lime	3991	
lime-shale	4150	
sand	4226	
lime-shale	4272	
lime w/shale	4316	
lime	4698	
lime w/shale	4737	
lime-shale	4775	
lime	4803	
lime w/shale	4826	DST 4765-4826 Open 1 hr. Shut
lime	4850	in 20 min. Rec. 10' mud. IBHP 0#,
lime-chert	4890	FFBHP 0#/20 min. FP 0-0#.
lime	4906	
cherty lime	4915	
lime-chert	4924	DST 4826-50 open 1 hr. Shut in
lime	4935	20 min. Rec. 30' mud. IBHP 285#,
Total Depth		FBHP 0#/20 min. FP 0-0#.
TOPS:		
Heebner	4066	DST 4580-90 Open 25 min. Shut in
Toronto	4105	20 min. Gas to surf. in 2 1/2 min.
Douglas	4125	Gauged after 5 min - 555,000 CFG,
Douglas sand	4147	8 min. - 416,000 CFG 10 min. -
Lansing	4268	310,000 CFG. Mud to surf. in 11
B/Kansas City	4664	min. IBHP 1780#, FBHP 1780#/20
Massey	4729	min. FP 843-1270#. Oil to surf.
Mississippian	4831	in 1e min.
Kinderhook	4902	