

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


2-32-15 W

Company- NATIONAL COOPERATIVE REFINERY ASSN.  
Farm- Skinner "C" No. 3

SEC. 2 T. 32 R. 15W  
NW NE SW

Total Depth. 4935'  
Comm. 5-24-58 Comp. 6-14-58  
Shot or Treated.  
Contractor. Aylward Drilling Company  
Issued. 11-8-58

County Barber  
KANSAS



CASING:  
8 5/8" @ 200' w/175 sx.  
5 1/2" @ 4932' w/50 sx.

Elevation. 1963' KB

Production. 250 BOPD

Figures indicate Bottom of Formations.

sand	60
sand & red rock	85
red rock & sand	110
Gyp rock - hard	128
red rock & gray shale	202
red rock	800
red rock & gyp	1300
red rock & shale	1450
shale & shells	2120
lime & shale	2200
mostly lime	2260
lime	2820
lime & shale	4150
sandy shale	4255
lime	4704
shale & lime	4738
lime	4766
lime w/shale streaks	4788
lime w/some shale	4817
lime	4865
lime - cherty	4915
lime	4935
Total Depth	4935

DST 4865-95 (Corrected to 4859-89)  
Good str. blow w/gas to surf. in 4".  
Gauged 362,000/5", 28,000/10". Oil in  
13". IBHP 1534#/20". FBHP 1525#/20".  
FP 870#-1172#.

TOPS:	
Heebner	4076
Toronto	4092
Douglas	4112
Douglas Sand	4142
Lansing	4255
B/Kansas City	4699
Massey	4721
Basal Penn. Cong. Sand	4790
Miss.	4815
Kinderhook	4904

DST 4714-38 (Corrected to 4708-32)  
Open 1 hr. Vry wk. blow dying in  
several min. Rec. 12' mud. IBHP  
115#/20", FBHP 45#/20". FP 25#-45#.

DST 4796-4840 (corrected to 4790-  
4834). Open 1 hr. Gas to Surf. in  
5". Gauged 439,000 in 15" & 465,000  
remainder of hr. IBHP 1738#/20".  
FBHP 1658#/20". FP 120-130#.

DST 4840-65 (Corrected to 4834-59)  
Open 1 hr. Gas to surf. in 7". Gaug-  
ed 76,000 in 10". 44,000/15", not str.  
enough to gauge after 15". Flowed oil  
in 55". IBHP 1652#/20". FBHP 1528#/  
20". FP 315#-912#.

