

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


3-32-15W

Company: Aylward Drilling Company ET AL
Farm: Skinner "D" No. 1

SEC. 3 T. 32 R. 15W
SE SE NE

Total Depth. 4901'
Comm. 8-26-57 Comp. 9-11-57
Shot or Treated.
Contractor: Aylward Drilling Company,
Issued. 12-21-57

County Barber KANSAS



Elevation. 1981' R. B.

Production. 11,000,000 CFG.

CASING:

8 5/8" @ 200' W/170 sks. cem.
5 1/2" @ 4901' W/150 sks. cem.

Figures indicate Bottom of Formations.

sand	70
red rock w/strks of gypsum	370
red bed & rock	1000
red rock & red bed	1125
salt	1185
shale & shells	2180
lime & shale	2345
lime & shale w/anhydrite	2440
lime & shale	2828
shale & lime	2960
kune & shale	3210
mostly shale, some lime	3320
shale & lime	3685
lime & shale	3830
lime w/shale	3913
sand, lime & shale	3974
lime & sand	4050
lime w/sand	4118
lime & shale	4193
lime & sand	4254
lime w/shale	4326
lime	4720
lime w/shale	4742
lime	4901
Total Depth	

#1 4800-30 Open 1 hr. gas to surf. in 2 min., gauged 734,000 in 5 min., dec. to 275,000 CFG after 1hr. Rec. 50' GOM. FP 135#-75#. IBHP 1575#/30 min. FBHP 1125#/30 min.

#2 4830-66 Open 30 min. Gas to surf. in 1 1/2 min., gauged 2,830 MCFG/5 min., inc. to 3,880 MCFG/20 min., sprayed oil after 25 min. Rec. 150' Mdy oil. FP 675#-745# IBHP 1625#/20 min.-FBHP 1610#/20 min.,

Tops: Electric Log.

Elgin Sand	None	
Heebner Shale	4077	4079
Base/Oread	4113	4121
Douglas Sand	4140	4141
Lansain	4259	4262
Base/ Kan. City	4692	4699
Mississippian	4798	4800
Rotary Total		
Depth	4901	4903

Drill Stem Test: