

3 - 32 - 15 W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- Aylward Drilling Co., Et Al.
Farm- Skinner "D" No. 3

SEC. 3 T. 32 R. 15W
NE NE SE

Total Depth. 4926'
Comm. 10-17-57 Comp. 11-2-57
Shot or Treated.
Contractor. Aylward Drilling Co.,
Issued. 4-12-58

County Barber
KANSAS



CASINO:
8 5/8" @ 222' W/190 sks. cem.
5 1/2" @ 4925' W/100 sks. cem.

Elevation. 1996' RB.

Production. 37 BOPD.

Figures indicate Bottom of Formations.

sand	50
red rock & Gypsum	965
red bed	1585
red rock & shells	1915
shale & lime	2210
lime	2510
lime & shale	2650
lime	2750
lime & shale	3535
shale W/some lime	3675
lime	3755
shale W/lime	3835
lime & shale	3875
lime	3979
lime & shale	4114
lime & sandy lime	4152
lime	4719
lime W/shale	4832
lime	4870
lime & Chat	4880
lime	4926 RTD
Total Depth.	

Drill Stem Test:

- #1 4818-80 Open 15 min. Gas to surf.
In 1 min. (Gauged 3,310 MCFG/2 min.,
3,780/5min.) Flowed mud/7min., fl.
oil/10 min. Rec., 200' oil in pipe.
IBHP 1635#/30 min. FBHP 1625#/30 min.
FP 1430#-1470#.
- #2 4880-4926 Open 20 min. No blow. Rec.
15' mud. IBHP 55#/20 min. FBHP 75#/20
min. FP 40#-40#.

Geological Tops:

Heebner Shale	4099
B/oread	4139
Douglas Sand	4190
Tonganoxie sand	4264
Lansing	4280
B/Kansas City	4720
Mississippian	4816
Rotary Total Depth	4926