

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


3-32-15W

Company- AYLWARD DRILLING COMPANY ET AL
Farm- Skinner "D" No. 4

SEC. 3 T. 32 R. 15W
SW SW SE

Total Depth. 4903'
Comm. 6-16-58 Comp. 7-4-58
Shot or Treated.
Contractor. Aylward Drilling Co.
Issued. 10-4-58

County Barber
KANSAS



CASING:

8 5/8" 290' w/250 sx. cem.
5 1/2" 4884' w/75 sx. cem.

Elevation. 1996 RB

Production. 200 BOPD

Figures Indicate Bottom of Formations.

sand	50
red rock	95
sand	125
red rock and Gypsum	300
red bed and shells	930
anhydrite	1051
shale and shells	1165
salt	1210
shale and lime shells	1301
shale and shells	1970
shale w/lime streaks	2160
mostly lime w/some shale	2330
lime	2630
lime w/shale	2920
lime and shale	3045
shale and lime	3165
shale w/lime	3385
shale & lime	3470
lime & shale	3665
shale and lime	3720
lime and shale	3918
mostly lime - some shale	3965
lime and shale	4048
lime w/shale	4103
lime and shale	4173
sandy lime and shale	4280
lime	4689
lime w/shale	4716
lime	4809
lime w/shale	4848
lime, very little shale	4903
Total Depth	

GEOLOGICAL TOPS

Heebner Shale	4120
Base Oread	4157
Douglas Sand	4201
Lansing	4302
Base of Kansas City	4740
Mississippi	4831

NO Electric Log Tops
DST 4861-4903 Open 35 min. Gas/2 1/2 in.
428 MCFG/5", 214 MCFG/10", fl. mud/10",
fl. 0.11/12", Rec. 35 BO from flowing & in
drill pipe. IBHP 1540#/20", FBHP 1530#/30"
FP 875#-1325#.