

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


3-32-15W

Company- AYLWARD DRILLING COMPANY ET AL
Farm- Skinner "D" No. 5

SEC. 3 T. 32 R.15W
NE SW SE

Total Depth. 4940'
Comm. 8-8-58 Comp. 8-27-58
Shot or Treated.
Contractor. Aylward Drilling Co.
Issued. 11-8-58

County Barber
KANSAS



Elevation. 2019' RB

8 5/8" @ 287' w/250 sx.
5 1/2" @ 4940' w/75 sx.

Production. 37 BOPD

Figures Indicate Bottom of Formations. 3,000,000 CFG

sand	74
red rock & gyp	287
gyp & red rock	430
red rock & gyp	1150
shale & shells	1850
lime & shale	2295
lime	2550
lime & shale	2660
lime w/shale	2710
lime & shale	2875
shale & lime	2960
lime w/shale	3060
lime & shale	3120
shale & lime strks.	3245
shale w/lime	3350
lime & shale	3430
shale & lime	3635
lime & shale	3772
lime w/some shale	3835
lime & shale	4045
mostly lime - some shale	4062
lime & shale	4234
sdv lime & shale	4268
lime & shale	4332
mostly lime - some shale	4396
lime	4845
cherty lime	4883
lime	4940 RTD
Total Depth	

DST 4626-45 (Straddle test from 4807) Open 1 hr. Wk. blow. Rec. 45' watery mud. IBHP 1498#/20", FBHP 855#/30", FP 35#-43#.

DST 4876-4903 Open 40 min. Gas surf. in 2 min., gauged 2,930 MCFG/5", 4,735 MCFG/15", leveled off at 4,925 MCFG/30". Rec. 60' Mdy & Gsy Oil. IBHP 1545#/20", FBHP 1528#/30" FP 887#-1030#.

DST 4894-4940 Open 45 min. Gas surf. /5", gauged 275 MCFG/8", 186 MCFG/15". Flowed mud/35", flowed oil/40". IBHP 1540#/20", FBHP 1533#/20". FP 420#-995#.

TOPS:
Heebner Shale 4130
Base/Oread 4166
Douglas Sand 4208
Tonganoxie Sand 4300
Lansing 4308
Base/ K.G. 4752
Mississippian 4838