

2-32-15W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AYIWARD DRILLING CO. ET AL
Farm- Skinner "D" No. 7

SEC. 3 T. 32 R. 15W
SW SE SW

Total Depth. 4882'

Comm. 1-15-59

Comp. 1-30-59


County Barber

KANSAS

Shot or Treated.

Contractor. Aylward Drlg.

Issued. 4-4-59



CASING:

8 5/8" 306' cem w/225 sx.
5 1/2" 4867' cem w/75 ax.

Elevation. 1979' RB

Production. 150 BOPD

Figures indicate Bottom of Formations.

sand & clay	35
red rock	60
red rock & gravel	150
gyp	190
red rock & gyp	910
Anhydrite	945
shale & shells	1470
shale w/lime	1540
shale w/vry little lime	2000
shale	2150
lime	2510
lime & shale	2625
lime	2670
lime & shale	2850
shale & lime	3030
shale w/some lime	3180
shale & lime	3540
lime & shale	4096
lime w/shale	4148
shale & sand	4233
lime & shale	4295
lime	4666
lime w/some shale	4704
lime	4724
lime & shale	4772
lime w/shale	4811
lime & shale	4816
lime	4861
cherty lime	4882
Total Depth	

DST 4057-82', op 1½ hr., gas to surf.
3" gauged 872 MCFG. Flowed oil/1 hr.
22 min. IBHP 1450#/20", FBHP 1410#/30".
FP 260#-810#.

TOPS:

Heebner Shale	4100
Base Oread	4136
Lansing	4277
Base Kansas City	4725
Mississippi	4816