

3-32-15W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AYLWARD DRILLING CO. ET AL
Farm- Skinner "D" No. 9

SEC. 3 T. 32 R. 15W
SW SW SW

Total Depth. 4940'
Comm. 9-20-60 Comp. 10-4-60
Shot or Treated.
Contractor. Aylward Drlg.
Issued. 11-19-60

County Barber
KANSAS



Elevation. 2000' KB

Production. Dry

CASING:

8 5/8" 280' cen w/225 sx.

Figures Indicate Bottom of Formations.

sandy clay	70
red bed	120
sand	130
red bed & shale	160
red bed	170
gyp	195
red bed, shells & shale	750
red bed & shale	1146
shale & shells	1580
shale	1700
shale & lime	2165
lime	2540
lime & shale	2660
lime	2725
lime & shale	3000
shale & shells	3100
shale & lime	3205
shale	3240
shale & shells	3450
shale	3595
shale & lime	3695
shale w/some lime	3820
shale & lime	3945
lime & shale	4065
shale	4152
lime & shale	4295
lime	4809
lime & shale	4873
dolomite	4940
Total Depth	

DST 4880-4910', op 30 min., Wk. b1./4".
Rec. 30' mud, IBHP 337#/20", FBHP 67#/15",
FP 44-44#.

DST 4910-40', op 30 min., Wk. b1/3",
Rec. 15' mud. IBHP 491#/20", FBHP 67#/15",
FP 22-22#.

TOPS:

Heebner	4125
Douglas Sand	4183
Lansing-Kansas City	4303
Base Kansas City	4747
Marmaton	4767
Mississippi	4830

DST 4833-80', op 30 min, wk. b1./10 mins.,
Rec. 50' mud. IBHP 156#/20", FBHP 111#/15".
FP 44-67#.