

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


3-32-15W ✓

Company- AYLWARD DRILLING CO.
Farm- Skinner "D" No. 10

SEC. 3 T. 32 R. 15W
C NW SE

Total Depth. 4912'
Comm. 9-29-64 Comp. 10-14-64
Shot or Treated.
Contractor. Co. Tools
Issued. 1-9-65

County Barber
KANSAS



Elevation. 1992 DF

Production. GA 1,200,000 CFGPD

CASING:

8 5/8" 280' cem. w/250 sx.
5 1/2" 4910' cem. w/200 sx.

Figures indicate Bottom of Formations.

Surface Clay & Sand	105
Red Rock & Shale	410
Shale & Shells	520
Red Rock & Shells	876
Shale	1675
Shale & Shells	2125
Lime	2730
Shale	2810
Lime & Shale	3265
Lime	3345
Lime w/Shale	3480
Lime	3820
Lime & Shale	4250
Sand	4280
Lime	4881
Chert & Lime	4905
Lime	4912

Rotary Total Depth

TOPS-Sample	
Heebner	4097
Base Oread	4131
Upper Douglas Sand	4184
Lower Douglas Sand	4256
Lansing-Kansas City	4277
Base Kansas City	4718
Mississippian	4810

DST#1. 4257-80. Op. 90" GTS/34"
Rec. 400' M&GCO, plus 20' SW
IBHP 1526#/30", FBHP 1396#/30"
FP 56#-178#

DST#2. 4820-81. Op. 1 hr. GTS/
2 1/2" Gauged 770,000 CFG/5", 1,
000,000 CFG/10", stablilized.
Rec. 210' GCM, IBHP 420#/30"
FBHP 402#/30", FP 149#-149#

DST#3. 4881-4912. Op. 60" Rec.
15' mud. IBHP 168#/30", FBHP
93#/30", FP 19#-28#