

8-32-15W ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SINCLAIR OIL & GAS COMPANY
Farm- T. L. Welsh "B" No. 1

SEC. 8 T. 32 R.15W
SW NE SW

Total Depth. 4925'
Comm. 4-22-1960 Comp. 5-11-1960
Shot or Treated.
Contractor. Garvey Drilling Company
Issued. 8-18-1962

County Barber
KANSAS



Elevation. 1932' DE.

Production. 5,587,000 CFG.

CASING:

10 3/4" @ 309' W/350 Sks. Cem.,
4 1/2" @ 4921' W/250 Sks. Cem.,

Figures Indicate Bottom of Formations.

Surface Soil & Red Bed	30
Red bed, Gypsum & Shells	240
Red Bed & Gypsum	310
Shale & Sand	1430
Anhydrite	1450
Shale & Lime	1845
Shale & Shells	1875
Lime & Shale	2455
Lime	2665
Lime & Shale	2765
Lime	3050
Shale & Lime	3250
Lime & Shale	3657
Lime	4038
Lime & Shale	4067
Lime	4338
Lime & Chert	4731
Lime	4776
Mississippi Chert	4810
Mississippi Lime	4925
TOTAL DEPTH	4925

TOPS:	SCOUT	
	Lansing	4236
	Marmaton	4656
	Mississippi	4757

SINCLAIR OIL & GAS COMPANY

State Geological Survey
WICHITA BRANCH
8-32-15W

P. O. Box 466
Chase, Kansas
July 27, 1960

RECEIVED
STATE CORPORATION COMMISSION
JUL 29 1960
CONSERVATION DIVISION
Wichita, Kansas

State Corporation Commission
State of Kansas
211 North Broadway
Wichita 2, Kansas

Gentlemen:

This is to advise that the following gas well has been completed:

OPERATOR: Sinclair Oil & Gas Company
LEASE: T. L. Welsh "B"
WELL NO: 1
LOCATION: 1650' from West and 1650' from South lines of SW/4 of Sec. 8-32S-15W, Barber County, Kansas.
PURCHASER: Not Connected
FIELD: Perry Ranch Pool
PRODUCING FORMATION: Mississippi Chert
TOPOF PRODUCING FORMATION: 4761'
PRODUCING FORMATION 4761' to 4784'
TOTAL DEPTH: 4925'
PLUGGED BACK TOTAL DEPTH: 4885'

ACIDIZED: Mississippi formation 4761 to 4784' with 500 gallons mud acid. Acid Petro-Fraced Miss. formation thru perforations 4761 to 4784' with 10,000 gallons jelled acid and 10,000# sand. - 5-19-60

PRODUCTION TEST:

Date - 5-20-60
How produced - Flow
Oil Produced - None
Gas Produced - 5,587 Cu. ft. thru 3/4" choke
Length of test - 24 hours.

Yours very truly,

C. B. York

CBY/r