

## KANSAS DRILLERS LOG

State Geological Survey  
WICHITA, BRANCHAPI No. 15 — 007 — 20,377  
County Number

Operator

Sands Drilling Co.

Address

912 Philtower Bldg, Tulsa, Oklahoma

Well No.

#1

Lease Name

D. W. Skinner Trust

Footage Location

660

feet from (N) 36 line

1980

feet from (E) 36 line

Principal Contractor

DNB Drilling

Geologist

Bob Sandridge

Spud Date

12-19-75

Total Depth

4971'

P.B.T.D.

Date Completed


1-1-76

Oil Purchaser

S. 9 T. 32 R. 15 W

Loc. 1980' FEL &amp; 660' FNL

County Barber

640 Acres  
N

Locate well correctly

2018

Elev.: Gr.

DF KB 2023'

## CASING RECORD

Report of oil strings set—surface, intermediate, production, etc.

| Purpose of string | Size hole drilled | Size casing set (in O.D.) | Weight lbs/ft. | Setting depth | Type cement | Sacks | Type and percent additives |
|-------------------|-------------------|---------------------------|----------------|---------------|-------------|-------|----------------------------|
| Surface           | 12-1/4            | 8-5/8                     | 29             | 215           | regular     | 200   | 3% CC                      |
|                   |                   |                           |                |               |             |       |                            |
|                   |                   |                           |                |               |             |       |                            |
|                   |                   |                           |                |               |             |       |                            |

## LINER RECORD

## PERFORATION RECORD

| Top, ft. | Bottom, ft. | Sacks cement | Shots per ft. | Size & type | Depth interval |
|----------|-------------|--------------|---------------|-------------|----------------|
|          |             |              |               |             |                |
|          |             |              |               |             |                |
|          |             |              |               |             |                |

## TUBING RECORD

| Size | Setting depth | Packer set at |  |  |  |
|------|---------------|---------------|--|--|--|
|      |               |               |  |  |  |


## ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

| Amount and kind of material used                          | Depth interval treated |
|---|------------------------|
| Plugged w/50 sks regular cmt. from 250'-100', 15 sks 40'- |                        |
| surface, 5 sks in rat hole & mouse hole.                  |                        |
|   |                        |

## INITIAL PRODUCTION

|  |              |   |                        |                       |  |
|--|--------------|---|------------------------|-----------------------|--|
| Date of first production<br>DRY                    |              | Producing method (flowing, pumping, gas lift, etc.) |                        |                       |  |
| RATE OF PRODUCTION<br>PER 24 HOURS                 | Oil<br>bbls. | Gas<br>MCF  | Water<br>bbls.         | Gas-oil ratio<br>CFPB |  |
| Disposition of gas (vented, used on lease or sold) |              |   | Producing interval (s) |                       |  |

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

| Operator   |  | DESIGNATE TYPE OF COMP.: OIL, GAS,<br>DRY HOLE, SWDW, ETC.:          |            |
|--|--|--|------------|
| Well No.<br><div>1</div>   | Lease Name<br><div>D. W, Skinner Trust</div>   | <div>Dry Hole</div>  |            |
| S <div>9</div> T <div>32</div> R <div>15</div> <div>R</div> <div>W</div>   |  |  |            |
| <b>WELL LOG</b><br>Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.   |  | SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION. |            |
| FORMATION DESCRIPTION, CONTENTS, ETC.  | TOP  | BOTTOM   | NAME DEPTH |
| <div>DST #1    4853-4971'</div> <div>IH 2582</div> <div>IF 83-102, 15 min.</div> <div>ISI 914, 30 min.</div> <div>FF 102-120, 60 min.</div> <div>FSI 1081, 120 min.</div> <div>FH 2563</div> <div>BHT 119°</div> <div>GTS in 18 min of second flow</div> <div>Recovered 160½ GCM</div> <div>T/ Mississippian</div> | 4854   | (±2830)  |            |
| USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.  |  |  |            |
| Date Received  | <div> <br/>           Signature<br/>           Manager Drilling &amp; Production<br/>           Title<br/>           January 12, 1976<br/>           Date         </div> |  |            |

State Geological Survey  
WICHITA, BRANCH

15-001-20377

9-32-15W

DRILLERS' LOG

SANDS DRILLING COMPANY  
No. 1 D. W. Skinner Trust  
C NW NE, Sec. 9-32S-15W  
Barber County, Kansas

Elev:

Commenced: 12-19-75  
Completed: 1- 1-76

Surface Casing: 208' of  
8-5/8" cemented w/200 sx  
common cement, 3% cc.  
12-19-75

| <u>FORMATION</u> | <u>DEPTH</u>    |
|------------------|-----------------|
| Surface Hole     | 0 - 215         |
| Shale            | 215 - 2254      |
| Shale & Lime     | 2254 - 2415     |
| Lime & Shale     | 2415 - 3140     |
| Shale & Lime     | 3140 - 3350     |
| Shale            | 3350 - 3570     |
| Lime & Shale     | 3570 - 3980     |
| Shale & Lime     | 3980 - 4185     |
| Lime & Shale     | 4185 - 4519     |
| Lime             | 4519 - 4799     |
| Shale & Lime     | 4799 - 4853     |
| Cherty Lime      | 4853 - 4940     |
| Lime & Shale     | 4940 - 4971 RTD |

I do hereby certify that the foregoing statements are true and correct  
to the best of my knowledge and belief.

D N B DRILLING, INC.

*James L. Donelson*  
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 9th day of January, 1976.

*Ella Priess*  
Ella Priess, Notary Public

