

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


10-32-15W

Company—AYLWARD DRILLING COMPANY
Farm—Skinner "W" No. 1

SEC. 10 T. 32 R. 15W
NW NW NE

Total Depth. 4946'
Comm. 5-6-58 Comp. 5-23-58
Shot or Treated.
Contractor. Aylward Drilling Co.
Issued. 10-4-58

County Barber
KANSAS



Elevation. 2002 RB

Production. 200 BOPD

CASING:

8 5/8" 209' w/175 sx. cem.
5 1/2" 4928' w/75 sx. cem.

Figures indicate Bottom of Formations.

sand and clay	65
red rock	150
red rock and gypsum	940
red rock and shale	1545
shale and shells	1950
shale and lime	2250
shale and shells	2270
lime	2370
lime w/some shale	2485
lime	2743
lime and shale	2840
lime	2940
lime w/shale	3150
lime and shale-	3495
lime	3570
lime and shale	3760
lime	3805
lime w/some shale	3907
lime and shale	3991
shale and lime	4064
lime and shale	4244
shale	4286
sand and shale	4355
lime	4691
lime and shale	4745
lime	4770
lime w/shale	4809
lime w/chert	4835
lime	4914
cherty lime	4946
Total Depth	

DST 4842-4920 Open 30 Min. Rec. 35' Mud.
IBHP 28#/30", FBHP 40#/30". FP 28#-28#.
DST 4920-46 Open 2 hr. 5 min. Gas to
surf. 14", too wk. to gauge. Rec. 880'
oil. IBHP 1570#/20", FBHP 1430#/30".
FP 50#-285#.

GEOLOGICAL TOPS:

Heebner Shale	4137
Base of Oread	4176
Douglas Sand	4191
Lansing	4317
Base of Kansas City	4764
Mississippi	4859