

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


11-32-15W

Company- AYLWARD DRILLING CO. ET AL
Farm- Skinner "X" No. 1

SEC. 11 T. 32 R. 15W
C SW SE

Total Depth. 5034'
Comm. 6-15-65 Comp. 6-29-65
Shot or Treated.
Contractor. Co. tools
Issued. 11-6-65

County Barber
KANSAS



Elevation. 2033' K.B.

8 5/8" 280' w/250 sx cem.
5 1/2" 5033' w/100 sx cem.

Production. 8,400 MCFGPD & small
amt. oil.

Figures Indicate Bottom of Formations.

soil	30
sand	70
Gyp, soil	120
red bed	410
shale	1530
shale, lime stks	2140
shale, lime	2295
lime	2395
lime w/shale brks	2540
lime	2660
lime w/shale btrks	2750
lime	2970
shale w/lime stks	3205
shale, lime	3530
shale w/lime stks	3800
shale, lime	4035
shale	4127
shale, lime	4145
shale, sand	4278
lime	4814
lime, shale	4897
lime w/shale	4993
lime	5034
Total Depth	

34 MCFG/14". Rec. 120' GCM.
IBHP 783#/30" - FBHP 95#/30"
FP 57#-76#

DST 4970-93 Op. 30" GTS/1"
Gauge 3,880 MCFG/5", 4,800
MCF/8", Sprayed mud/16". Rec.
30" Cl. oil IBHP 1705#/30"-
FBHP 1705#/30" FP 764#-801#.

DST 4993-5003 Op. 1 hr. GTS/3 1/2"
Gauge 416 MCFG/5", 499 MCF/20"
588 MCF/60". Rec. 300' Cl. oil
& 70' Muddy oil. IBHP 1705#/30"-
FBHP 1705#/30". FP 104#-142#.

DST 5003-13 Op. 1 hr. Rec. 5'
mud w/few spots oil IBHP 123#/30"-
FBHP 76#/30" FP 19#-19#.

TOPS: GEOLOGICAL

Heebner	4111
Douglas	4145
Brown lime	4253
Lansing	4277
Kansas City	4491
B/Kansas City	4720
Marmaton	4740
Choteau	4886
Kinderhook	4913
Maquoketa	4950
Viola	4969

DST 4717-4814 Op. 1 hr. GTS
4" Gauge 155 MCFG/60", 77 MCF/9",