

14-32-15W

WELL LOG BUREAU- KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- FERGUSON OIL CO. ET AL
Farm- Larkin No. 2

SEC. 14 T. 32 R.15W
C SW SE

Total Depth. 5013'

Comm. 6-22-65

Comp. 7-5-65


County Barber

KANSAS

Shot or Treated.

Contractor. Walters Drlg. Co.

Issued. 4-2-66



CASING:

8 5/8" 272' cem w/200 sx.
5" 5000' cem w/150 sx.

Elevation. 1983' KB

Production. 265 BOPD, NW

Figures Indicate Bottom of Formations.

surf. clay & sand	150
shale & sand stks.	275
red bed	930
Anhydrite	990
shale & shells	1010
shale	1390
shale & shells	2115
lime & shale	2305
lime	2400
lime & shale	2905
shale	3105
lime & shale	3295
shale & lime	3595
lime & shale	3785
shale & lime	4040
lime & shale	4175
shale & lime	4261
lime & shale	4460
lime	4815
lime & shale	4854
lime	4900
lime & chert	4955
lime	5013 RTD

Total Depth

TOPS: LOG

Heebner	4061
Douglas Shale (Sample)	4091
Brown Lime	4201
Lansing	4223
Kansas City	4433
Base Kansas City	4664
Marmaton	4668
Mississippi Chert	4722
Mississippi Lime	4750
Chouteau	4847
Kinderhook	4886
Maquoketa	4921
Viola	4944