

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


14-32-15W

Company- AYLWARD DRLG, ETAL
Farm- Skinner "Z" No. 2

SEC. 14 T. 32 R. 15W
C NE NW

Total Depth. 5090
Comm. 4-8-65 Comp. 4-23-65
Shot or Treated.
Contractor. Aylward Drlg.
Issued. 9-11-65

County Barber KANSAS



CASING:

8 5/8" 279' 250 sx.

Elevation. 2031 KB

Production. 126 BOPD, NW

Figures Indicate Bottom of Formations.

surface clay	85
sand	110
red bed	156
Gyp. & red bed	190
red bed	1015
shale	1222
shale & shells	1820
shale	2060
shale w/lime streaks	2180
lime	2210
shale & lime	2390
lime	2740
shale & lime strks.	3085
lime & shale	4258
lime	4879
shale	4910
lime	5090
TOTAL DEPTH	

TOPS: Log

HEebner	4122
Douglas	4146
Lansing	4280
Base Kansas City	4722
Marmaton	4734
Mississippian	4792
Maquoketa	4960
Viola	4977
Simpson	5085
TD	5089

DST 4965-79 Opn. 1 hr. GTS/20" Gauge 34000
CFG. Rec. 20" mud, IBHP failed- FBHP 1563#/30"
FP 33-33#.

DST 4980-98 Opn. 25" GTS/2" Gauge 2.530
MCF/4", 2.19 MCF/5", 2.060 MCF/10"
sprayed mud/13", sprayed oil/17" IBHP 1678#/30"-
FP 1003-1020#

DST 5078-99 Opn. 30 min. Rec. 16' sulphur wtr.
IBHP 1723#/30"-FBHP 1705#/30", FP 166-768#

DST 4722-70 Opn. 45", Rec. 210' Gasin pipe
25' mud, IBHP 41#, FP 41-41#

DST 4788-4808 GTS 1 1/2" gauge 4.26 MCF/5",
6,160/10", 2.060 "/30". Rec. 125' GCSW. FP
1607-1590#, IBHP 1731#/30"-FBHP 1723#/30"