

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

14-32-15W

COMPANY ALYWARD DLG. COMPANY

SEC. 14 T. 32 R. 15W

LOC. C NWNE

FARM SKINNER "2"

NO. 3

TOTAL DEPTH 4987

COMM. 4-27-65

COMP. 5-11-65

SHOT OR TREATED

CONTRACTOR ALYWARD DRIG.

ISSUED 7-16-66

COUNTY

BARBER
KANSAS

CASING

20

10

15

8 5/8

@ 274 W 275 SX

ELEVATION 2019

12

6

13

5

PRODUCTION 259 bopd

FIGURES INDICATE BOTTOM OF FORMATIONS

	From	To	Remarks
Surface Soil	0	30	Set 8 5/8" surface pipe @ 274'
Sand & Gyp Streaks	30	90	w/275 sacks.
Red Bed	90	150	
Gyp	150	190	Geological Tops:
Red Bed	190	1096	
Red Rock	1096	1180	Reebner 4102
Shale & Lime	1180	2050	Douglas 4134
Shale w/Lime Streaks	2050	2110	Brown Lime 4246
Lime	2110	2750	Lansing 4270
Shale	2750	2765	Choteau 4377
Shale & Lime	2765	2965	Kinderhook 4913
Shale w/Lime Streaks	2965	3025	Maquoketa 4949
Shale	3025	3765	Viola 4978
Shale & Lime	3765	4229	
Lime	4229	4775	DST 4710-45 Open 30"
Lime & Shale	4775	4810	Rec. 15' mud
Lime w/Shale Streaks	4810	4895	IBHP 910/30"-FBHP 580/30"
Shale & Lime	4895	4958	FP 33-33#
Lime	4958	4987 T.D.	

DST 4953-70 Open 30"
Rec. 30' mud
IBHP 330/30"-FBHP 330/30"
FP 33-33#

DST 4974-87 GTS/3"
Gauged 367,000 CFG/3"
Flowed oil in 55"
IBHP 16780/30"-FBHP 16070/30"
FP 274-612#

Set 5 1/2" casing @ 4981 w/100 sack.

No log run.

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.