

14-32-15W ✓


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas

Company- FERGUSON OIL CO.  
Farm- Swayden No. 1

SEC. 14 T. 32 R. 15W  
C NE SW

Total Depth. 5061'  
Comm. 1-27-65 Comp. 2-14-65  
Shot or Treated.  
Contractor. Walters Drilg. Co.  
Issued. 5-8-65

County Barber  
KANSAS



CASING:

Elevation. 1996' D.F.

3 5/8" 216' w/160 sx cem.  
5 1/2" 5051' w/200 sx cem.

Production. Fol 200 BOPD & 3% wtr.

Figures Indicate Bottom of Formations.

shale, sand strks 220  
shale 1350  
sdy shale 1860  
shale, shells 2145  
lime, shale 2390  
lime 2505  
lime, shale 2650  
lime 2850  
lime, shale 3114  
shale, lime 3280  
shale, lime strks 3465  
shale, lime 3780  
shale 4050  
shale, lime 4150  
shale, lime, sand strks 4205  
lime 4460  
lime, shale 4525  
lime 4610  
lime, shale 4666  
lime 4745  
lime, shale 4765  
lime, sand, chert 4785  
lime 4820  
lime, shale 4936  
lime 5052  
sand 5056  
Rotary Total Depth

Kansas City 4466  
B/Kansas City 4690  
Marmaton 4709  
Conglomerate sand 4763  
Chouteau 4871  
Maquoketa 4937  
Viola 4954  
\* Simpson 5060

TOPS: SCOUT  
Heebner 4091  
\* Toronto 4099  
\* Douglas shale 4117  
Douglas sand 4162  
Lansing 4252

\* Sample tops.