

17-32-15W ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SINCLAIR OIL & GAS COMPANY
Farm- T. L. Welsh "C" No. 1

SEC. 17 T. 32 R. 15W
SW NE NW

Total Depth. 4935'
Comm. 6-28-1960 Comp. 7-18-1960
Shot or Treated.
Contractor. Barbour Drilling Company
Issued. 8-18-1962

County Barber
KANSAS



CASING:
10 3/4" @ 308' W/300 Sk. Cem.,
5 1/2" @ 4930' W/200 Sk. Cem.,

Elevation. 1947'

Production. 55 BOPD. 5,500,000
CFG.

Figures Indicate Bottom of Formations.

Surface Clay	50
Shale & Red Bed	135
Shale	310
Shells & Shale	965
Shale & Shells	1710
Shale	1940
Shale & Shells	2150
Lime	2330
Lime & Shale	2407
Lime	2480
Lime & Shale	3030
Shale & Lime	3290
Lime & Shale	3800
Lime	3905
Shale, Lime & Strks. of Sand	3985
Shale & Lime	4150
Shale & Sand	4180
Sand & Shale	4192
Shale	4260
Lime	4664
Lime & Shale	4820
Lime & Chert	4860
Lime & Shale	4901
Lime	4935
TOTAL DEPTH	4935

TOPS:

ELECTRIC LOG

Heebner	4074
Douglas Shale	4103
Douglas Sand	4152
Lansing	4247
Mississippi	4777
Total Depth	4935

17-32-15W

SINCLAIR OIL & GAS COMPANY

P. O. Box 466
Chase, Kansas
July 27, 1960

State Corporation Commission
State of Kansas
211 North Broadway
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUL 29 1960
CONSERVATION DIVISION
Wichita, Kansas

Gentlemen:

This is to advise that the following gas well has been completed:

OPERATOR: Sinclair Oil & Gas Company

LEASE: T. L. Welsh "C"

WELL NO.: 1

LOCATION: 990' FNL and 990' FEL of the NW/4 of Sec 17 - 32S - 15W, Barber County, Ka.

PURCHASER: Not Connected

FIELD: Perry Ranch Pool

PRODUCING FORMATION: Mississippi Chert

TOP OF PRODUCING FORMATION: 4777'

PRODUCING FORMATION: 4820' to 4850'

TOTAL DEPTH: 4935'

PLUGGED BACK TOTAL DEPTH: 4895'

ACIDIZED: Mississippi formation 4820 to 4850 with 500 gallons mud acid. Acid-Petrofraced Mississippi formation thru perforations 4820 to 4850 with 20,000 gals jelled acid and 20,000 lbs sand, 7-24-60.

PRODUCTION TEST:

Date - 7-26-60

How produced - Flow

Oil produced - None

Gas produced - 5,500 MCFD thru 3/4" choke

Length of test - 24 hours

Yours very truly,

C. B. York

C. B. York

CBY/j