

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


22-32-15W

Company - CHAMPLIN REFG. CO.
Farm - Mills No. 1.

SEC. 22 T. 32 R. 15 W
SE SW NE
1650' FEL 2310' FNL NE $\frac{1}{4}$

Total Depth. 5100'
Comm. 8-27-43 Comp. 10-4-43
Shot or Treated.
Contractor.
Issued. 1-22-44

County. Barber
KANSAS



CASING:
10 $\frac{3}{4}$ " 480' Cem.
5 $\frac{1}{2}$ " 4964' Cem.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

red bed-sand	0-210	Perf. 20 shots spaced
sand-red bed-shale	524	1' apart 4835-54
red bed-shale-shells	1105	2 BWP
red bed-shale	1470	Set Lane Wells plug
shale-shells	2070	@ 4800
shale-lime	2405	Perf. 8 shots 4872-90
lime	2470	Bailed $\frac{1}{4}$ BW w/sh oil
lime-shale	3655	500 Gals. & no help
shale	3710	Set Lane Wells plug
shale-lime	3790	@ 4770
shale	4035	Perf. 10 shots 4745-55
lime-shale	4065	no shows
shale	4155	Perf. 3 shots 4261-63
shale-lime	4230	no shows
lime	4300	Perf. 3 shots 4263-67
lime-shale	4390	1000' wtr in 1 hr
lime	4680	
lime-shale	4705	
lime	4745	
shale-lime	4780	
lime	4795	
shale-lime	4815	
lime	4880	
lime-chert-shale	4900	
shale-lime	4985	
shale	5008	
shale-lime	5013	
lime	5100	
Total Depth.		

Geological Tops:

Lansing-K.C.	4268
Mississippi	4812
Kinderhook	4950
Viola	5076