

26-32-15W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CHAMPLIN REFG. CO.
Farm - Hildebrand No. 5.

SEC. 26 T. 32 R. 15 W
CS $\frac{1}{2}$ NE SE
1650' fSL & 660' fEL SE $\frac{1}{4}$

Total Depth. 5314' (5312 DF)
Comm. 6-7-44 Comp. 7-12-44
Shot or Treated.
Contractor.
Issued. 8-19-44

County. Barber
KANSAS



CASING:
10 $\frac{3}{4}$ " 480' Cem. LI

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

sand, shells, & red bed	0-280
sand, shale	500
shale, shells	2265
anhydrite	2295
lime, shale	2307
lime	2450
lime, shale	2550
lime	2595
lime, shale	3950
shale	4150
shale, sand	4190
steel line measurement	4190-4193
sand, lime	4193-4235
shale, lime	4295
lime	4710
shale, lime	5000
lime (cored)	5020
lime	5022
lime (cored)	5047
lime	5120
sand (cored)	5127
sand	5131
sand (cored)	5136
shells, shale	5230
shale, sand	5250
lime (cored), shale	5261
lime	5280
lime (cored)	5291
lime	5314
Total Depth	

Tops:
Lansing 4230
Miss. 4760
Kinderhook 4790
Viola 4988 D.F.

Drill Stem Test
T.D. 5045-Pkr. 4991 open 1 hr.
10 mins. Recovered nothing.
Simpson 5125

Drill stem test T.D. 5134-Pkr
5125 Open 30 mins. Recovered
450' NaCl-H₂O
Simpson dolo. 5244
Arbuckle 5269
T.D. 5312 D.F. Spot fresh mud
from 4000 to 5312' TD
Ran Schlumberger Survey