

27-32-15W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

Company - CHAMPLIN REFINING COMPANY
Farm - Baird No. 4

SEC. 27 T. 32 R. 15W
CS₁ SE SE
330' fr. SL, 560'
fr. ML of SE/4

Total Depth. 4946'
Comm. 9-15-48 Comp. 10-20-48
Shot or Treated.
Contractor.
Issued. 12-11-48

County. Barber
KANSAS



CASING:

8 5/8" 795' cem w/300 sx.
5 1/2" OD 4953' cem w/250 sx.

Elevation. 1884 *Ind.*

Production. 328 BO

Figures Indicate Bottom of Formations.

| | |
|---------------------|------|
| redbed and shells | 500 |
| sand, shale, shells | 700 |
| redbed and shells | 795 |
| redbed and salt | 1255 |
| salt and shells | 1450 |
| shale and shells | 1865 |
| anhydrite | 1895 |
| shale and shells | 2012 |
| lime and shale | 3040 |
| shale and shells | 3165 |
| shale and lime | 4915 |
| lime | 4946 |
| total depth | |

Tops:

| | |
|------------------------------|-------|
| Lansing | 4178' |
| Erosional Mississippi | 4730 |
| Maquokata Dolomite | 4912 |
| Viola, Coarsely Xyln lime | 4926 |