

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

27-32-15W


COMPANY CHAMPLIN PETROLEUM CO.

SEC. 27 T. 32 R. 15W
 LOC. C NW NW

FARM W.F. Baird NO. 5

TOTAL DEPTH 5121'
 COMM. 6-2 -66 COMP. 6-18-66
 SHOT OR TREATED
 CONTRACTOR Leben Drlg., Inc.
 ISSUED 10-15-66

COUNTY Barber
 KANSAS



CASING

20	10	
15	8 5/8	244' w/175 sx cem.
12	6	
13	8 4 1/2"	3970' w/125 sx cem.

ELEVATION 1852' D.F.

PRODUCTION Flo. 34 BOPD
 & 258 MCFGPD

FIGURES INDICATE BOTTOM OF FORMATIONS

0	20	Shale, Gypsum
20	233	Redbed, Sand, Gypsum
233	775	Redbed
775	910	Shale
910	945	Anhydrite
945	1975	Shale, Shells
1975	2640	Lime, Shale
2640	3320	Shale, Lime
3320	4272	Lime, Shale
4272	4700	Lime
4700	4762	Lime, Chat
4762	4796	Lime, Chert
4796	4801	Lime
4801	4856	Lime, Shale
4856	4920	Lime
4920	4970	Lime, Shale
4970	5067	Lime
5067	5121	Sand, Lime
	5121	<u>RTD - Set 4 1/2" Casing</u>

TOPS: SCOUT

Heebner	4002
Douglas	4030
Lansing	4164
B/Kansas City	4624
Marmaton	4638
Cherokee	4720
Mississippi	4731
Kinderhook shale	4812
Kinderhook lime	4884
Woodford	4929
Viola	4960
Simpson	5088
Simpson sand	5096