

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Plotted
~~27-32-15W~~

Company - CHAMPLIN REFINING COMPANY
Farm - Hildebrand No. 9

SEC. 27 T. 32 R. 15W
NE SW SE NE
2116' fNE1 & 705' fNE1 NE $\frac{1}{4}$

Total Depth. 4903'
Comm. 12-8-46 Comp. 1-11-47
Shot or Treated.
Contractor.
Issued. 5-24-47

County. Barber
KANSAS



Elevation. 1848 *act*

Production. Phy. Pot: 251 B0

CASING:

10 $\frac{3}{4}$ " 500' Cem. w/250 sx
5 $\frac{1}{2}$ " 4903' Cem. w/350 sx

Figures Indicate Bottom of Formations.

sand & rod bed	0-510
rod bed, shale & shells	1050
shale & shells	1720
salt & shells	1905
shale & shells	1965
lime shells	2010
lime & gyp	2185
lime	2220
lime cherty	2240
lime	2290
shale & lime	2345
lime	2410
shale & lime	2465
lime & chert	2500
lime	2545
lime & shale	2755
shale	2840
shale & lime	2920
shale	3000
lime & shale	3145
shale	3370
lime	3560
shale & lime	3610
lime	3640
shale & lime	4105
lime	4580
shale	4595
lime & shale	4760
shale	4790
shale & lime	4870
chert & lime	4901
lime	4903
Total Depth	

Tops:

Lansing	4075
Kansas City	4140
Miss.	4630
Viola	4872
Crystalline Viola	4888