


State ks. Field \_\_\_\_\_  
 Company Rinehart County Comanche  
 Farm Schutte No. 1  
 Sec. 12 Twp. 32 Range 16

Spot C SE SE NW  
 Contractor D+M D+lg  
 Remarks P.D. Miss



Comm. 12/4/58 Comp. 3/11/59  
 Elev. DF 1465 GL \_\_\_\_\_ KB \_\_\_\_\_ TD 4975 PB 4938  
 Pay Miss 4868 - 82

I.P. F5380 + 4000/24' Press. \_\_\_\_\_  
 Casing Record: 13 3/8 <sup>905 g 500 mf</sup> \_\_\_\_\_ 7"  
20" \_\_\_\_\_ 10 3/4 273/200 5 1/2" 4975/250  
16" \_\_\_\_\_ 8 5/8 \_\_\_\_\_

Loc.	Sample	Log
DEC 17	Lan 4287	Hb 4114
DEC 30	Miss 4848	st. ss 4276
DST 4918-88	slt sand	Lan 4287
op 2' gts 6"	so	Miss 4846
g. 134 mf / 15"		
g. 124 mf / 20"		
g. 88 mf / 2'		
rec 95' gcm +		
15' hot gcm		
15IP 1775/30		
FP 60-60 FSIP		
1635/30		
DST 4888-4919		
op 1' wb 6lo		
rec 40' 59cm w/ 50cm		
free oil 15IP 1795/?		
FP 35-45 FSIP 105/30		
ATD 4975 log.		
city. <u>Miss</u>		
JAN 7 <u>CO</u> P96/ 4864-88		
gts ind. 80 mf + 50		
5P 12' boiled 4 BO A/1000		
sub 2 BXW PH + 4 BO PD		

~~SP MOCT~~

JAN 14 ~~P~~ WOCT to rework

JAN 21 JAN 28 MI sg/1500 G Latex  
attay sg CO 4890 subg.

FEB 4 no rpt.

FEB 11 sg/475 latex, CO 4938,

perf 84/4868-82, A/1/veo  
sub 142 BO + 1.26 BWPH/3 md  
prec/7500 A, sd/1500, sub  
200 BFI (18% oil + 82% water),  
1,000 mcf/6 hrs; ~~Installing~~  
~~surface equip.~~

FEB 18 T fld 56 BF (40% oil 60% water)  
gas est 1,500 mcf/2 hrs. fld  
12 BF 50% oil gas est 1,500 mcf/6'

SI SITP 1390\* SI  
F 182.10 BO + 90 BO/3 days

@ rate 60.70 BO + 30 BW

gas est 1,500 mcf/12'

FCP 580 ~~total~~

MAR 4 allow F 25 BO + 36 BW/24'

gas g 1,500 mcf FCP 560\*

MAR 11 F 55 BO + 40 BW 1" ch/24'

gas g 500 mcf (gas 3/0)

Miss 4868-82