

State Kansas Field Stevens
Company Joseph E. Newman County Meade
Farm Plains Townsite No. 1
Sec. 16 Twp. 32S Range 30W

Spot SE SE

Contractor Cherokee 5700' Miss

Remarks

			0

Comm. Comp.

Elev. DF 2761 GL KB TD PB

Pay

I.P. Press.

Casing Record: 13 3/8 7" 5790'/cem

20" 10 3/4 5 1/2"

16" 8 5/8

Spudded & drilling ?	Log	Datum
FEB 9 <u>Tite hole</u>		
FEB 10 <u>64702 (29-60)</u>		
FEB 17 <u>45200 tite hole</u>		
FEB 24 <u>" "</u>		
MAR 2 <u>" "</u>		
MAR 9 <u>" "</u>		
MAR 23 <u>" "</u>		
MAR 30 <u>" "</u>		
APR 6 <u>" "</u>		
APR 13 <u>" "</u>		
APR 20 <u>" "</u>		
APR 27 <u>" "</u>		
MAY 4 <u>" "</u>		
MAY 11 <u>" "</u>		
MAY 18 <u>" "</u>		
MAY 25 <u>" "</u>		
JUN 1 <u>" "</u>		
JUN 8 <u>" "</u>		
<u>perf 5738-43 / 5728-</u>		
<u>32' / 9,800' MCF</u>		
<u>5663-77, TD 5745</u>		
<u>PB 5677</u>		
<u>60 5783, 5764-</u>		
<u>74, A/3500, BP</u>		
<u>5751, 5738-42</u>		
<u>5728-32</u>		
<u>30" BD g 9,702 MCF</u>		
<u>A/2000, BP 5700</u>		

619516

5663-77, sub NO SHO

COSYSI, BP 5205

5170-71

A/500

subly oil
POP

JUL 20

A-7-29
 MAP NO. 84 ✓
 STATE Kansas COUNTY Meade SEC. 16 Twp 32S Rge 30W
 OPERATOR Joe Newman & Harvest Queen Mills LOC. SE SE
 WELL NO. 1 FARM NAME Plains Townsite 565 FT. FROM S LINE
 TOOL Stevens 865 FT. FROM E LINE
 FR. 1-27-60 SPUD 1-23-60 COMP. 6-29-61 of Sec.

CONT./GEOL. Cherokee Tools Bob Gensch-Geol

COMPLETION RECORD			
NAME PRODUCING INTERVAL	FROM - TO	PERF. W/HOLES	TREATMENT RECORD
a <u>Marmaton</u>	<u>5150-63</u>	<u>36</u>	<u>500 Ac</u>
b <u>Morrow</u>	<u>5663-77</u>	<u>48</u>	
c <u>Chester</u>	<u>5728-42</u>	<u>32</u>	<u>2000 Ac.</u>
d			

a I. P. OIL/DIST. WTR. GAS M.C.F.P.D. CHK. HRS.
 b " * See Body of Ticket " "
 c " " " " "
 d

D & A ()

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____
 GOR. _____ GR. _____ PBDT 5751 TD 5806
 SIZE DEPTH CASING - CEMENT RECORD SIZE DEPTH W/SAX.
10" 1590 Cem
7" 5790 Cem

OPERATOR Newman & Harvest Queen WELL NO. #1 Plains Townsite ELEV 2763 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Morrow Shale	5545		Herrington	2698	
Chester	5578		Winfield	2810	
Ste Genevieve	5810		Upper Ft. Riley	2870	
			Heebner	4407	
			Lansing	4527	
			Marmaton	5114	
			Marmaton	5136	
			Cherokee	5355	
			Atoka	5430	
			Morrow	5645	
			Morrow Sand	5657-62	
			Morrow Sand	5664-81	
			Chester	5725	

Spud 1-23-60, 10" @ 1590 w/cem.
 RTD 5806, logs, 7" @ 5790 w/cem.
 P/40/Chester/5764-74, 5000 Ac, Rc Fm wtr, Set plug @ 5751.
 P/16/Chester/5738-42, 16/Chester/5728-32, Ga 9702 MCF/30 mins, 2000 Ac, Set plug.
 P/48/Morrow/5663-77, (no test). CO to 5751. Set Plug @ 5205.

P/24/Marmaton/5150-56, 12/Marmaton/5160-63, 500 Ac. CO plgs.

*Completion information is subject to question as well was drilled tight.

Permission to triple complete from Chester 5728-42, Morrow 5663-77 and Marmaton 5150-63 has been granted by the State of Kansas.

No production information is available on the Marmaton zone 5150-63 which is producing oil.

Panhandle Eastern Pipe Line is buying gas from the Morrow 5663-77 and Chester 5728-42.

From the Morrow: 8265 MCF in March, 6526 MCF in April, 6341 MCF in May.

From the Chester: 6190 MCF in March, 2938 MCF in April, 3555 MCF in May.

Any additional information will be reported as received.

LIBERAL ELECTRIC LOG TOPS

619516

2763 KB

Heebner 4411 (-1648)

Lansing 4528 (-1765)

Marmaton 5134 (-2371) 8,300 MCF

Morrow 5644 (-2881)

Sand 5657 (-2894) 20/24; 6,200 MCF

Chester 5725 (-2962)

TD 5809