

KANSAS

IMPORTANT
Kans. Geo. Survey request
samples on this well.

WELL COMPLETION REPORT AND
DRILLER'S LOG

API No. 15 — 033 — 20,349

Operator

Hummon Corp.

Address

400 One Main Place Wichita, Kansas 67202

Well No.

#1-26

Lease Name

Gregg

Footage Location

1980 feet from ~~XX~~ (S) line1980 feet from ~~XX~~ (W) line

Principal Contractor

D. R. Lauck Oil Company

Geologist

John Carnes

Spud Date

5-4-80

Date Completed

5-14-80

Total Depth

5215

P.B.T.D.

Directional Deviation


Oil and/or Gas Purchaser

State Geological Survey
WICHITA BRANCH
AUG 8 1980
RECD

S. 26 T. 32 R. 17 ~~K~~ W

Loc. C NE SW

County Comanche

640 Acres
N

Locate well correctly

2058

Elev.: Gr. 2061 KB 2063

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{4}$	8-5/8	28#	386	Common	250	2% gel 3%cc
Production		4 $\frac{1}{2}$ "	10 $\frac{1}{2}$ #	5214	60-40 Poz	125	10% salt, 3/4 of 1% CFR2, 6/10ths of Halad 9, 20 Bbls salt water ahead

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	Glass jets	5138-44'

TUBING RECORD

4 SSB 5134-36'

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used			Depth interval treated
500 gal. MCA			5138-44'

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)				
RATE OF PRODUCTION PER 24 HOURS	Oil bbis.	Gas MCF	Water bbis.	Gas-oil ratio	CFPB	
Disposition of gas (vented, used on lease or sold)					Producing interval(s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

rator

Hummon Corporation

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
gas

Well No. #1-26	Lease Name Gregg	
S 26 T 32 R 17 ^{EE} W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<p>DST #1: 5103-5145'</p> <p>OP 60-60-60-120</p> <p>GTS 15 min.</p> <p>Inc. to 26,800 CFGPD 1st blow</p> <p>2nd blow 101,000 CFGPD dec. & Stab. 73 600 CFGPD in 40 min</p> <p>Rec. 345' GCM</p> <p>FP 68-119</p> <p>SIP 1748-1748</p>			ELECT. LOG TOPS	
<p>DST#2: 5144-5170'</p> <p>OP 45-60-45-60</p> <p>Weak blow 1st open</p> <p>No blow 2nd open</p> <p>Rec. 120' mud w/ no show</p> <p>FP 34-76</p> <p>SIP 1671-1629</p>			Lecompton Heebner Lansing B/KC Pawnee Ft. Scott Miss. RTD 5215	4066 -2003 4284 -2221 4470 -2407 4970 -2907 5035 -2972 5066 -3003 5135 -3072 LTD 5221

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received



Signature

Wilber Berg

Title

5-15-80

Date