

16-32-18W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- J. M. HUBER CORPORATION
Farm- Herd No. 1

SEC. 16 T. 32 R. 18W
C NE SW

Total Depth. 6016'
Comm. 5-12-62 Comp. 7-5-62
Shot or Treated. ^{6?}
Contractor. Reaves Drlg.
Issued. 6-19-65

County Comanche
KANSAS



CASING:

Elevation. 2151' RB

13 5/8" 535' cem w/ 550 sx
4 1/2" 5397' cem w/ 250 sx

Production. 1,350,000 CFG

Figures Indicate Bottom of Formations.

sand-shells	200
red bed	850
red bed-shells	1246
shale-lime	1850
shale-lime & anhydrite	2596
lime-shale	3124
shale-lime w/ chalk strks	3501
shale-lime	3930
sandy shale	4215
shale-sandy lime	4375
lime-shale	4790
lime	4880
lime-shale strks	5145
lime	5240
lime shale strks	5641
shale-lime	5760
lime	5920
shale-lime	5940
lime-shale	5960
sand-shale	6016 RTD
Total Depth	

TOPS: SCOUT

Heebner	4326
Brown lime	4510
Lansing	4537
Base Kansas City	4880
Marmaton	5035
Cherokee	5135
Mississippi	5192
Kinderhook	5643
Viola	5684
Simpson	5957