

15-033-20315

P
State Geological Survey
KANSAS DRILLERS LOG
WICHITA BRANCH

API No. 15 —————
County Number

Operator
KEENER OIL COMPANY

Address
320 S. Boston, Suite 406, Tulsa, Oklahoma 74103

Well No. 1 Lease Name Richard Bird

Footage Location
1740 feet from (N) ~~XX~~ line 1500 feet from (E) ~~2500~~ line

Principal Contractor Geologist
Gabbert-Jones Mr. George A. McCaleb


Spud Date Total Depth P.B.T.D.
9/19/79 5275 5275

Date Completed Oil Purchaser
10/2/79 Dry hole

S. 28 T. 32S R. 19 ~~EX~~
W
Loc. 150' E & 90' S NE SW NE

County Comanche

640 Acres



Elev.: Gr. 1932

DF 1935 KB 1937

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Conductor	17-1/2"	13-3/8"	48	85'	Reg.	250	CaCl 3%
Surface	12-1/4"	8-5/8"	20	610'	Howco Lite Reg.	200 350	CaCl 3%

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement
None		

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at
None		

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
None					
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

operator KEENER OIL COMPANY	DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole
--------------------------------	---

Well No. 1	Lease Name Richard Bird
---------------	----------------------------

S <u>28</u> T <u>32S</u> R <u>19</u> XK W

WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.	SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.
--	---

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Herrington	2373	(-436)		
Cottonwood	2895	(-958)		
Topeka	3706	(-1769)		
Elgin Sand	4046	(-2109)		
Heebner	4164	(-2227)		
Lansing-Kansas City	4384	(-2447)		
Base Kansas City	4792	(-2855)		
Cherokee	5006	(-3069)		
Miss. Detrital	5074	(-3137)		
Miss. Lime	5096	(-3159)		
R.T.D.	5275	(-3338)		
DST #1 - 5050-5108 45"-60"-60"-60" Strong blow, dec. to weak at end of test. Rec. 135' mud. 1 HP - 2600 PSI I.F.P. 485-429 (some plugging) ISIP 634 PSI F.F.P. 252-243 PSI FSIP 491 PSI FHP 2691				
NOTE: NO OPEN HOLE LOGS RUN.				
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received	<i>F.W. Weener</i> Signature Production Superintendent Title 10/19/79 Date
---------------	--