

15-191 - 20729

5-32-2W  
SE SE NW

DUNBAR DRILLING INC.  
5252 NORTH BROADWAY  
WICHITA, KANSAS 67219  
(316) 832-0501

February 28, 1978

INDIAN WELLS OIL COMPANY  
Herb Herbal  
620 South Douglas  
Lyons, Kansas 67554

Re: Hill # 3  
SE SE NW Section 5-32S-2W  
Summer County, Kansas

DAILY REPORT

1/15/78 tear down rig; move; and rig up  
1/16/78 drill rat hole  
1/17/78 set 8 5/8" surface pipe @ 256 feet  
1/18/78 rig down  
1/19/78 rig down  
1/20/78 rig down  
1/21/78 install blow out preventor  
1/22/78 rig down  
1/23/78 rig down - work on pump and mud line  
1/24/78 work on pump and commence drilling  
1/25/78 1201 feet = shale and shells  
1/26/78 1857 feet = shale and lime streaks  
1/27/78 2404 feet = shale and lime; 1/2 hour company (circulating)  
1/28/78 2780 feet = lime and shale  
1/29/78 3210 feet = lime and shale  
1/30/78 3582 feet = shale and Kansas City lime  
1/31/78 3797 feet = lime and shale  
2/1/78 3903 feet = shale and lime; 10 1/2 hours company time (circulating, mix  
mud, come out for Drill Stem Test # 1)  
2/2/78 24 hours company time (Drill Stem Test # 1 = On bottom @ 3:00 A.M.  
open 30 minutes-closed 45 minutes-open 60 minutes-closed 60 minutes  
start out @ 6:45 AM)  
2/3/78 4068 feet = Mississippian lime  
2/4/78 4208 feet = Mississippian lime  
2/5/78 4315 feet = shale and lime and total depth; 7 hours company time  
(circulating and logging)  
2/6/78 8 hours company time (logging); set 3952 feet of 5 1/2" casing