

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas

13-32-2W

Company- J. E. MORRIS
Farm- Roy

No. 1

SEC. 13 T. 32 R. 2W
NE NE SE

Total Depth. 3798'

Comm. 1-7-58


Comp. 1-31-58

Shot or Treated.

Contractor. Rex & Morris Drlg.

Issued. 8-9-58

County Sumner
KANSAS



Elevation. 1264' DF

Production. 25 BOPD

CASING:

8 5/8" 433' cem w/270 sx.

5 1/2" 3391' cem w/150 sx.

Figures Indicate Bottom of Formations.

surface hole	433
shale & lime	640
lime & shale	1220
shale & lime	1715
lime & shale	1835
shale & lime	2150
lime & shale	2335
shale & lime	2510
lime	2560
lime & shale	2742
sand	2850
shale & sandy lime	2930
shale	3092
lime	3355
shale & lime	3555
lime & shale	3642
shale Conglomerate	3716
chat	3735
lime	3798
Total Depth	

TOPS: SCPUT

Lansing 2740

Kansas City 3092

Mississippi 3715

Mississippi Dolomite 3735

Ran Schlumberger (IES, MLL)

Perforate 24 shots 3284-90

Acid 2000 gal.