

**KANSAS DRILLERS LOG**

API No. 15 — 033 — 20,226  
County Number

S. 31 T. 32S R. 20 <sup>E</sup>/<sub>W</sub>  
Loc. 660' FSL & 660' FEL  
County Comanche

Operator  
Texas Oil & Gas Corp.

Address  
200 West Douglas, Suite 300, Wichita, Kansas 67202


Well No. 1 Lease Name Ewy

Footage Location  
660 feet from (N) (S) line 660 feet from (E) (W) line

Principal Contractor Xplor Drilling Company Geologist High Plains Consulting Ltd.

Spud Date 5-29-77 Total Depth 5285' P.B.T.D. N/A

Date Completed 6-7-77 Oil Purchaser N/A



Locate well correctly  
Elev.: Gr. 1894'  
DF 1899' KB 1902'

**CASING RECORD**

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2"	8 5/8"	24#	630'	Common	600	2% Gel, 3% CaCl

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A			
<b>TUBING RECORD</b>			N/A	N/A	N/A
Size	Setting depth	Packer set at			
N/A	N/A	N/A			

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
N/A	N/A

**INITIAL PRODUCTION**

Date of first production N/A Producing method (flowing, pumping, gas lift, etc.) N/A

RATE OF PRODUCTION PER 24 HOURS  
Oil N/A bbls. Gas N/A MCF Water N/A bbls. Gas-oil ratio N/A CFPB

Disposition of gas (vented, used on lease or sold) N/A Producing interval (s) N/A

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator  
Texas Oil & Gas Corp.

DESIGNATE TYPE OF COMP.: OIL, GAS,  
DRY HOLE, SWDW, ETC.:

Well No.  
1

Lease Name  
Ewy

Dry Hole

S 31 T 32S R 20 E  
W

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,  
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Herrington	2380	-478		
Krider	2402	-500		
Winfield	2453	-549		
Towanda	2503	-601		
Fort Riley	2577	-657		
Florence	2606	-704		
Wreford	2728	-826		
Beattie	2903	-1001		
Cottonwood	2943	-1041		
Foraker	3086	-1184		
Onaga Shale	3238	-1336		
Wabaunsee	3330	-1428		
Stotler	3425	-1523		
Tarkio	3506	-1604		
Howard	3653	-1751		
Topeka	3782	-1880		
Queen Hill	4039	-2137		
Heebner	4185	-2283		
Douglas Shale	4295	-2393		
Iatan	4382	-2480		
Lansing	4390	-2488		
Stark	4768	-2866		
Swope	4777	-2875		
Hertha	4818	-2916		
B/KC	4861	-2959		
Marmaton	4905	-3003		
Cherokee	5046	-3144		
Morrow Shale	5150	-3248		
Mississippi	5162	-3260		
TD	5285	-3383		

DST #1, 5192-5224', (Mississippi), w/results as follows:

IFP/30": 55-55#, weak blow thru-out  
 ISIP/45": 55#  
 FFP/15": 55-55#, weak blow, died in 15"  
 FSIP/30": 55#  
 Rec 30' mud.

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

*Harold A. Brown*  
 Harold A. Brown Signature

District Geologist

Title  
 6-13-77

Date