

5-109W MAP NO. 84 SEC. 20-32S-30W
STATE Kansas COUNTY Meade LOC. C SW SW
OPER. Wm. Gruenerwald, Chicago, Ill FT/FR _____ LINE _____
WELL #1 FARM Hayden FT/FR _____ LINE _____
POOL Plains ELEV. _____ GR. 2777 DF 2779 KB _____
CONT. Graham - Michaelis GEOL. Tom Wright
CO. INT. PTD 6300' Miss test
F.R. 4-10-64 SPUD. 4-12-64 COMP. 5-12-64
TD. 6110 FM. St. L PBTD. _____
COMP. RECORD 8-5/8" @1596' w/375 Sx. D&A _____

Data Inc.

KB Log Tops:

No upper hole tops called.

Mrw	5524	-2745
U/Mrw sd	5524	-2745
B/Mrw sd	5536	-2757
2nd Mrw sd	5546	-2767
B/2nd Mrw sd	5560	-2781
Chest	5564	-2785
St. Gen	5818	-3039

St. L	5958	-3179
LTD	6109	-3330

DST #1(Mrw)5517-67, Op $1\frac{1}{2}$ hrs. R 3420' SW, ISIP 1807#/30', IFP 707#, FFP 1692#, FSIP 1840#/30'

RTD 6110', SJ Log, WLT #1(St. L) 5969 $\frac{1}{2}$ -72, Op 1 hr, R .07 Cfg, + 200 cc. wtr. = 41% form wtr. (Perm too low to prod.)ISIP -NA SP 50#, FSIP 50#/30'.

WLT #2(St. L)5959 $\frac{1}{2}$ -62, Op 1 hr, R 1150 cc wtr. (= 6% form wtr. (zone cal as wtr.)ISIP 1800#/30', SP 50#, FSIP 50#/30'.

D&A 5-5-64 COMPLETED 5-5-64