

2704 Gr

MAP NO. K-84 A-4-6 ELEV. 2715 DF
 STATE Kansas COUNTY Meade SEC. 20 Twp 32 S Rge 29 W
 OPERATOR Sinclair Oil & Gas Company LOC. C SW SW
 WELL NO. 3 FARM NAME M. E. Angell FT. FROM _____ LINE
 OL Angell (PD 5700) FT. FROM _____ LINE
 FR. 2-9-61 SPUD 2-18-61 COMP. 3-30-61
 CONT./GEOL. Gabbert & Jones # 2

NAME PRODUCING INTERVAL		COMPLETION RECORD		PERF. W/HOLES		TREATMENT RECORD	
		FROM	TO				
a							
b							
c							
d							

d I. P. OIL/DIST. _____ WTR. _____ GAS _____ M.C.F.P.D. _____ CHK. _____ HRS. _____
 b " " " " " "
 c " " " " " "
 d _____

D & A

D & A (X)

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____
 GOR. _____ GR. _____ PBTD _____ TD 5725

SIZE	DEPTH	CASING - CEMENT RECORD	SIZE	DEPTH	W/SAX.
<u>8-5/8"</u>	<u>1572</u>	<u>850</u>			
<u>4 1/2"</u>	<u>5668</u>	<u>225</u>			

OPERATOR Sinclair O & G WELL NO. 3 M. E. Angell ELEV. 2715 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Heebner	4367		Heebner	4362	
Lansing	4521		Lansing	4517	
Marmaton	5138		Marmaton	5127	
Morrow	5548		Cherokee	5228	
Morrow Sand	5580-84		Morrow	5542	
Morrow Sand	5592-99		Mississippian	5655	
Mississippian	5667				

Spud 2-18-61. 8-5/8" @ 1572 w/850 sx.

DST # 1 (Morr) 5572-5622, op 90 mins, gd blo T. O., rec 30' M,

ISIP 640/90 mins, FP 15-75, FSIP 1445/90 mins.

DST # 2 (Mor-Miss) 5620-75, failed.

DST # 3 (Mor-Miss) 5615-75, op 1 hr, wk blo/4 mins, rec 45' M,

ISIP 132/30 mins, FP 30-45, FSIP 90/30 mins.

RTD 5725, logs (Welex) to 5724. 4 1/2" @ 5668 (corr) w/225 sx.

MICT. CO to 5635.

P/24/5560-66, 20/5570-75, 44/5595-5606. 500 MA. Swb 1d/NS.

Frac 25,000 Ac X 25,000 sd. Swb 1d + 17 BOPD, gty 40°.

Ltr swb 1/2 BO + 1/2 BL/5 hrs. Ga TSTM, CP 150. Ltr swb 2 BO + 7 BL/6 hrs (non commercial). D & A 3-30-61 COMPLETE

LIBERAL TOPS

2704 GL

Winfield 2764 (+60)

Council Grove 2997 (-293)

Heebner 4384 (-1680)

Lansing 4516 (-1812)

Marmaton 5127 (-2423)

Morrow 5583 (-2879) T 72', Tss 12'

"S₂" Sand 5594 (-2890) 9/12, swb 2 BO + 7 Bld/6 hrs

Chester 5655 (-2951)

TD 5725 D & A.