

33-32-21W

**KANSAS GEOLOGICAL SOCIETY**  
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY J.M. HUBER CORPORATION


SEC. 33 T. 32 R. 21W

FARM York NO. 1

LOC. C NW/4

TOTAL DEPTH 5500'  
 COMM. 12-12-65 COMP. 12-30-65  
 SHOT OR TREATED  
 CONTRACTOR Gabbert-Jones, Inc.  
 ISSUED 5-14-66

COUNTY Clark



CASING  
 20 10  
 15 8 5/8 712' w/525 sx cem.  
 12 6  
 13 4 1/2 5393' w/150 sx cem.

ELEVATION 2022' D.F.

PRODUCTION FLO. 134 BOPD,

FIGURES INDICATE BOTTOM OF FORMATIONS

DEPTH	FORMATION	REMARKS
From	To	
0	190	RED BED
190	713	RED BED AND SHELLS RAN 18 JOINTS OF 8-5/8" CASING, SET @ 712' w/525 SACKS CEMENT.
713	870	RED BED AND SHELLS
870	1985	RED BED AND SHALE
1985	2300	SHALE AND SHELLS
2300	2930	SHALE AND LINE
2930	3095	LINE
3095	3795	SHALE AND LINE
3795	4100	LINE
4100	4365	LINE AND SHALE
4365	5188	LINE
5188	5330	LINE AND SHALE
5330	5500	LINE
5500	TD	RAN 165 JOINTS OF 4 1/2" CASING, SET @ 5393' w/150 SACKS CEMENT.

- TOPS: SCOUT 4340
- B/Heebner 4345
- Toronto 4345
- Lansing 4526
- Des Moines 5055
- Morrow 5314
- Mississippi 5364

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C NW/4 SECTION 33-32-21W, CLARK COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

*E. E. Hall*

E. E. HALL

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 31ST DAY OF DECEMBER, 1965, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THIS DAY AND