

15-025-20253

State Geological Survey

IMPORTANT
Kans. Geo. Survey request
samples on this well.

KANSAS DRILLERS LOG

API No. 15 — 025 — 20,253
County Number

Operator

Texas Oil & Gas Corp.

Address

300 - 200 West Douglas Wichita, Kansas 67202

Well No.

#1

Lease Name

Ewy "A"

Footage Location

1989 feet from (N) (S) line 660 feet from (E) (W) line

Principal Contractor

Xplor Drilling, Rig #1

Geologist

Robert L. Laymon

Spud Date

1-25-79

Total Depth

5285'

P.B.T.D.

N/A

Date Completed

3-9-79


Oil Purchaser

N/A

S. 36 T. 32 R. 21 E W

Loc. C NE SE

County Clark

640 Acres
N

Locate well correctly

Elev.: Gr. 1892'

DF KB 1900'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8-5/8"		633'	lite common	300 250	3% CaCl & 2% Gel
Production		2-7/8"	6.5#	5284'		150	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A	w/2 JSPF	N/A	5165-70'
TUBING RECORD					
Size	Setting depth	Packer set at			
N/A	N/A	N/A			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
N/A	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
8-9-79		flowing			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	N/A	bbls. 300	MCF None	bbls.	N/A
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
Northern Natural Gas			5165-70'		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

erator

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No. #1	Lease Name Ewy "A"	gas
----------------	-----------------------	-----

S 36 T 32 R 21 ^E_W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Herrington	2371	-471		
Topeka	3774	-1874		
Heebner	4192	-2292		
Douglas	4302	-2402		
Lansing	4404	-2504		
Swope	4806	-2906		
Hertha	4829	-2929		
Mississippi	5179	-3279		
DST #1, 5153-5175', (Morrow), w/results as follows: IFP/30": 622-447#, GTS in 1", 179 MCF/D ISIP/60": 1720# FFP/45": 633-455#, 2.9 MMCF/D decr. to 2.25 MMCF/D and stab. FSIP/90": 1605#				
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received

HAROLD A. BROWN

Signature

District Geologist

Title

May 3, 1979

Date