

State Kansas Field _____
 County Clark
 Company Shamrock Oil Co.
 Farm J. E. Stephens "I" Well No. "II"
 Sec. B14 Twp. 32S Range 21W
 fr N _____ fr E 2570' fr S L 1390' fr W _____
 of Sec. _____

Contractor Co. Tool

Remarks _____

Comm. 3-6-55 Comp. 5-18-55

Elev. 2024 DF T. D. 5249 P. B. _____

Pay 5232-46 Qty 53.1°

42 bopd
 I. P. 51,000 mcf R. P. _____

Casing Record: 13 3/8 _____ 7
 20 _____ 10 3/4 _____ 5 1/2 5248/300
 16 _____ 8 5/8 557/550

Date	Description	Notes
3-9-55	TTD 580', prep to run surface pipe.	Tops <u>Lang 4469</u> <u>Mann 4870</u> <u>Munsd 5230</u>
MAR 16 1955	<u>13 3/8 557/550</u> <u>8</u>	
MAR 23 1955	<u>φ 2836</u> <u>φ 3923</u>	
MAR 30 1955	<u>φ 4884 making try</u>	
APR 6 1955	<u>DST 5222-36 1/2 BHC 1" TAC</u> <u>on 1/4 mi. 4 1/2 mi gfs on 8 1/2 mi</u> <u>1st d 176 - 2 1/8 mcf</u> <u>Res 120' gcm w/ 5/8" sandstone sho</u> <u>at top FP 19-25" BHSIP 1720/30</u> <u>NH 2560</u>	
	<u>φ #1 5236-49 Res 11' 9"</u> <u>1" cra gum, fairly take sd w/ sat str</u> <u>in parts gd cut, odor & flavor</u> <u>4" md to res gum sd w/ excellent</u> <u>por, sat and st str & flavor, no odor</u>	

1' sd on above w/gd por str & flux.

3" md to esa gm sd on above w/sat str excellent flux & gd asphaltu odor

3' md to esa gm sd w/sat str. gd flux, asphaltu odor

DST 5231-49 5' BNC 1" THC on 15 min gts on 1 min

Heavy spray of oil & dist in 5 min

" " " " " " 10 min

max gas gauge 14,000 mf thru 4" flow line see 15' free oil, no water

FP 1650-1625 BHSIP 1795/30 HH 2620-759s

RTD 5249 Schl to 5248

7" 5248/300

Schl

WOET with rotary crown only 1040

APR 13 1955 ~~AT&T~~ CO 5248 well 1595-

56 / 5232-46 Hull 2394

run by 5247 Here. 2456

Swab & kicked off Koa 2498

Penn 3322

thru annuli of 24,600 mf Mo. 4116

thru Lang KC 4476

now 23,600 mf gas Mann 4860

wet w/oil Cch 5081

Man sh 5229

FCPIP 1010 " sd 5234

307m SETP 1510

SICP 1575

gas well

SI for barrel pressure test

guzzled approx 40,000 mf

Asalite open flow

4-20-55 ✓ 27 AM. 51,000 mf

42 BOPO thru 1/2" 3/4" 51 BHP 1825.7#

surface ch. ✓ 4 SEWAP 1570 # Guts 53.10