

25-32-22W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company. SUNRAY MID-CONTINENT OIL  
Farm- E. R. Martin No. 1

SEC. 25 T. 32 R. 22W  
C SW SW

Total Depth. 5443'  
Comm. 8-1-61 Comp. 8-20-61  
Shot or Treated.  
Contractor. Earl F. Wakefield  
Issued. 6-23-62

County Clark  
KANSAS



CASING:  
8 5/8" 625'

Elevation. 2026'

Production. Dry

Figures Indicate Bottom of Formations.

|                         |      |
|-------------------------|------|
| red shale               | 165  |
| gyp & shale             | 245  |
| blue shale & gyp        | 275  |
| red bed                 | 335  |
| gyp & shale             | 597  |
| shale                   | 999  |
| red bed & gyp           | 1440 |
| gyp, red & gry shale    | 1930 |
| shaley lime             | 2060 |
| Anhydrite, lime & shale | 2284 |
| Anhydrite & lime        | 2375 |
| lime & shale            | 2438 |
| Anhydrite, lime & shale | 2630 |
| lime & shale            | 2897 |
| Anhydrite, lime & shale | 2994 |
| Anhydrite, shale & lime | 3122 |
| lime & shale            | 3510 |
| chalky lime & shale     | 3676 |
| lime & shale            | 4428 |
| shale & lime            | 4508 |
| lime & shale            | 4601 |
| broken lime & shale     | 4658 |
| lime & shale            | 4695 |
| chalky lime & shale     | 4767 |
| lime & shale            | 4925 |
| lime                    | 5005 |
| lime & shale            | 5096 |
| lime                    | 5169 |
| lime & shale            | 5304 |
| shale & lime            | 5335 |
| lime & shale            | 5443 |
| Total Depth             |      |

|                  |      |
|------------------|------|
| TOPS: SCOUT      |      |
| Heebner          | 4272 |
| Toronto          | 4287 |
| Douglas          | 4315 |
| Lansing          | 4470 |
| Base Kansas City | 4964 |

|                     |      |
|---------------------|------|
| Marmaton            | 5011 |
| Cherokee            | 5154 |
| Mississippi Chester | 5346 |
| St. Genevieve       | 5369 |