


5-108W MAP NO. 84 SEC. 22-32S-29W
 STATE Kans. COUNTY Meade LOC. C NW NW
 OPER. Kewanee Oil Co., Wichita, Kansas FT/FR 5 LINE
 WELL #1 FARM Golliher 2703 FT/FR 2704 LINE
 COL Wildcat * ELEV. 2697 GR. 2699 DF 2704 KB
 INT. Garvey Drlg Tools GEOL. W. S. Spalding
 CO. 6400' Miss test
 F.R. 4/3/64 SPUD 4/6/64 COMP. 5/12/64
 TD. 6350 FM. St Lou PBTD.



Data Inc.

COMP. RECORD

8-5/8" @ 1479 w/950 sx.
 * 2 miles SW of Miss & Mrw Gas in Sanders Field
 D & A

Gr Spl Tops:	Gr Log Tops:	
CG 3050	Cg 3048	- 351 Chest 5698 -3001
Hb 4418	Hb 4416	-1719 St Gen 5961 -3264
Tor 4468	Lans 4578	-1881 St Lou 6049 -3352
Lans 4574	Marm 5180	-2483 LTD 6350 -3653
Marm 5183	Mrw 5624	-2927
Cher 5343		
Mrw 5618	DST #1 (CG) 3141-70, Op 45", R 75' VSGCM	
Ches 5677	300' WCM, ISIP 739#/60", IFP 99#, FFP 181#	
St Gen 5963	FSIP 730#/75"	

(Cont'd on back)

St L 6040	DST #2 (Mrw - Ches) 5697-5800, Misrun
RTD 6350	DST #3 (Mrw-Ches) 5708-5800, Op 1 hr.
	1700' GIP, R 100' SGCM, ISIP 1543#/60"
	IFP 42#, FFP 82#, FSIP 1818#/90"

RTD 6350, Log

DST #4 (Miss) 5864-6094 (Str Pkr) Op 15", SI/45", Op 45",
 SI/70", WB, R 120' M, ISIP 511#/45", IFP 55#, FFP 109#,
 FSIP 183#/70", D&A (4/30/64) COMPLETE

LIBERAL ELECTRIC LOG TOPS

2704 KB

Winfield 2800 (-103)
Council Grove 3050 (-353)
Heebner 4432 (-1735)
Toronto 4456 (-1759)
Lansing 4576 (-1879)
Marmaton 5178 (-2481)
Morrow 5632 (-2935)
Chester 5698 (-3001)
Ste. Gen 5968 (-3271)
St. Louis (Opr) 6050 (-3353)
TD 6350 D & A