

Bartel #1
C NW SE Sec. 7-32S-27W
MEAD COUNTY

8 5/8 @ 1452'
Commenced: 3/2/77
Completed: 3/16/77

KB 2524'
DF 2521'

	<u>E. Log Tops</u>	<u>Sub-Sea</u>
Council Grove	2966	-442
Heebner	4344	-1820
Toronto	4362	-1838
Lansing	4507	-1983
Marmaton	5074	-2550
Cherokee	5242	-2718
Morrow Sh.	5459	-2925
Morrow Sd.	5472	-2948
Chester	5519	-2995
St. Gene	5705	-3181
RTD	5670	
LTD	5750	-3226

Geologist: Don Huber

DST #1 4525 - 4554 Lansing
15/45/90/90
G.T.S.20" in 2nd flow
2nd flow
30" 17.2 MCF/day
60" 24.5 " "
90" 27.3 " "
F.P.'s 65-65/49-49#
C.I.P.'s 1521-1472#
Rec. 150' M.

DST #2 4927 - 4950 Morrow
30/45/60/60
FP's 354-691/806-1182#
CIP's 1651-1671 #
Rec. 2450' salt water

Completion:

4½ @ 4630'
perf. Lansing 4520-25'
250 G. 15% Spearhead acid

JUN 27 1985
State Geological Survey
WICHITA BRANCH

RECEIVED
STATE CORPORATION COMMISSION

JUN 27 1985

CONSERVATION DIVISION
Wichita, Kansas

C NE SE
SECTION 7-32S-27W
MEADE COUNTY, KANSAS

BARTTEL #1

BARTTEL 1

CONTRACTOR: RINE DRILLING COMPANY

STARTED: MARCH 1, 1977

COMPLETED: MARCH 19, 1977

L O G

Surface 0' - 41'
Red Bed 41' - 1452'

Red Bed & Shale 1452' - 2535'
Shale 2535' - 2595'
Lime & Shale 2595' - 5760'

JUN 27 1985
State Geological Survey
WICHITA BRANCH

Ran 30 jts. 8 5/8" csg. set @ 1445',
cmt. w/60 sx. lite, 2% cc, 1/4# flo
seal + 150 sx. H

Totco - 3/4° @ 500'; 1/2° @ 1013';
1/2° @ 1452'

Totco - 1/2° @ 1919'; 1/2° @ 2515'

Totco - 1° @ 2595'

Totco - 3/4° @ 3269'; 3/4° @ 3866';
1° @ 4554'


Ran 112 jts. 4 1/2" csg. set @ 4630'
cmt. w/50 sx. Class H, 8% gel, 12 1/2#
gilsonite, 10% salt +150 sx. 50-50 poz
mix, 10% salt, 12 1/2# gilsonite.

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

I, E. J. Rine, do hereby certify that the above is a true and accurate log of the Bartel #1,
located C of NE of SE of Section 7-32S-27W, Meade County, Kansas.


E. J. Rine, President

Subscribed and sworn to before me this 22nd day of March, 1977.


Carol J. Hladik, Notary Public

My Commission Expires: 10/31/79



RECEIVED
STATE CORPORATION COMMISSION

JUN 27 1985

CONSERVATION DIVISION
Wichita, Kansas