

WELL COMPLETION REPORT AND DRILLER'S LOG

State Geological Survey
KANSAS
WICHITA BRANCH

API No. 15 — 119 — 20511
County Number

Operator

Leben Oil Company

Address

P. O. Box 35528, Tulsa, OK 74135

Well No.

2

Lease Name

Rollins

Footage Location

330

feet from (N) line

330

feet from (W) line

Principal Contractor

Gabbert-Jones

Geologist

T. Jacobson

Spud Date

7/31/81

Date Completed

9/13/81

Total Depth

5798

P.B.T.D.

5757

Directional Deviation

None

Oil and/or Gas Purchaser

Panhandle Eastern Pipe Line


S. 28 T. 32S R. 29 W

Loc. NW NW NE

County Meade

640 Acres

N



Locate well correctly

Elev.: Gr. 2695

DF 2703 KB 2705

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	1470	Lite Class H	600 150	2% cc 2% cc
Production	7 7/8"	4 1/2"	10.5	5796	50/50 Poz	325	18% Salt 12 1/2# gilsonite/sx 3/4 of 1% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
None			4	90°	5624-32
TUBING RECORD			4	90°	5638-43
Size	Setting depth	Packer set at			
2 3/8"	5567	5567			


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

INITIAL PRODUCTION

Date of first production Not on line		Producing method (flowing, pumping, gas lift, etc.) Flowing			
RATE OF PRODUCTION PER 24 HOURS	Oil 0 bbls.	Gas 1500 MCF	Water 0 bbls.	Gas-oil ratio - CFPB	
Disposition of gas (vented, used on lease or sold) (Vented during test) To be sold			Producing interval(s) 5624-43		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Leben Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:		
Well No. 2	Lease Name Rollins	Gas		
S <u>28</u> T <u>32S</u> R <u>29</u> ^W				
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.		
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.				
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Toronto	4422		CBL	5732-3600
Lansing	4520		CDL & CNL	5798-4000
Marmaton	5172		DI	5792-1460
Morrow	5616			
USE ADDITIONAL SHEETS, IF NECESSARY TO COMPLETE WELL RECORD.				
Date Received	<div style="text-align: right; margin-bottom: 10px;">  </div> <div style="text-align: right;"> <div style="border-bottom: 1px solid black; width: 150px; margin-bottom: 5px;"></div> <div style="border-bottom: 1px solid black; width: 150px; margin-bottom: 5px;"></div> <div style="border-bottom: 1px solid black; width: 150px; margin-bottom: 5px;"></div> <div style="border-bottom: 1px solid black; width: 150px; margin-bottom: 5px;"></div> </div>			
	Signature Engineer Title 10/28/81 Date			