

TYPE

WICHITA BRANCH AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

SIDE ONE

Compt

30-32-29W

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

F Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5021 EXPIRATION DATE 6/30/84

OPERATOR Imperial Oil Company API NO. 15-119-20,639

ADDRESS 720 Fourth Financial Center COUNTY Meade

Wichita, Kansas 67202 FIELD

** CONTACT PERSON Cheryl McMillan PROD. FORMATION NA

PHONE 316/263-5205

PURCHASER NA LEASE ADELE

ADDRESS WELL NO. 1-30

DRILLING Eagle Drilling WELL LOCATION SW SW SE

CONTRACTOR 2310 Ft. from East Line and

ADDRESS P.O. Box 8609 330 Ft. from South Line of

Wichita, KS 67208 the SE (Qtr.) SEC 30 TWP 32S RGE 29 (E) (W).

PLUGGING Eagle Drilling

CONTRACTOR P.O. Box 8609

ADDRESS Wichita, KS 67208

TOTAL DEPTH 5940' PBTD NA

SPUD DATE 9-23-83 DATE COMPLETED 10-7-83

ELEV: GR 2710' DF KB 2723'

DRILLED WITH ~~XXXXXX~~ (ROTARY) (~~XXX~~) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE NA

Amount of surface pipe set and cemented 1601' DV Tool Used? NA


THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

WELL PLAT

(Office Use Only)

KCC
KGS
SWD/REP
PLG.



A F F I D A V I T

Robert C. Spurlock

that: _____, being of lawful age, hereby certifies

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Robert C. Spurlock
(Name)

SIDE TWO

ACO-1 WELL HISTORY (E)

OPERATOR Imperial Oil Company LEASE ADELE

SEC. 30 TWP. 32S RGE 29 (W)

FILL IN WELL INFORMATION AS REQUIRED:

WELL NO. 1-32

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<p>Check if no Drill Stem Tests Run.</p> <p>DST #1: 4538-4565 (60-60-60-60) IF 49-96 ISIP 1151 FF 96-128 FSIP 1086 Rec. 100'SW, 100'DM.</p> <p>DST #2: 5162-5180 (60-120-60-120) IF 86-118 ISIP 1528 FF 151-151 FSIP 1474 Rec. 1500'GIP, 60'OGCM, 30'SOCM, 60'SOCMW, 125'SW.</p> <p>DST #3: 5605-5629 (60-120-60-120) IF 64-43 ISIP 1323 FF 54-32 FSIP 1291 Rec. 45'M.</p> <p>DST #4: 5638-5661 (60-120-90-120) IF 86-75 ISIP 948 FF 86-75 FSIP 701 Rec. 15' Sli Gssy DM.</p> <p>DST #5: 5662-5705 (30-60-60-120) IF 75-54 ISIP 948 FF 54-54 FSIP 1765 Rec. 20' Sli GCM.</p>			<p>E-Log Tops:</p> <p>Heebner 4402 -1679 Toronto 4425 -1702 Lansing 4535 -1812 Stark Shale 4976 -2253 B/KC 5127 -2404 Marmaton 5161 -2438 Cherokee 5333 -2610 Atoka Shale 5576 -2853 Atoka Sand 5608 -2885 Morrow Shale 5634 -2911 Morrow B Sand 5639 -2916 Miss-Chester 5717 -2994 LTD 5942 -3219</p>	
If additional space is needed use Page 2, Side 2				

Report of all strings set—surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12½	8 5/8	24#	1601	Lite Common	500 200	3% CaCl, ¼# flocc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD					
Size	Setting depth	Packer set at			