

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


30-32-29W

Company- SINCLAIR OIL & GAS CO.
Farm- Angell No. 2

SEC. 30 T. 32 R.29W
C SW NE

Total Depth. 5730'
Comm. 6-17-60 Comp. 7-9-60
Shot or Treated.
Contractor. Garvey Drlg. Co.
Issued. 4-22-61

County Meade
KANSAS



CASING:
8 5/8" 1585' cem w/900 sx.
4 1/2" 5720' cem w/250 sx.

Elevation. 2710'

Production. 4,672,000 CFG

Figures indicate Bottom of Formations.

sand & shale	380
sand	450
red bed	880
shale & shells	975
sand	1200
shale & anhydrite	1485
anhydrite	1495
red bed & gyp	1587
shale	1610
shale & broken lime	2175
shale w/anhydrite strks	2545
lime, shale & chert	2665
lime	2875
lime w/chalky lime	2955
lime & shale	3069
lime, shale w/chalky lime	3180
chalky lime	3395
chalky lime & shale	3515
lime & shale	4295
shale w/lime streaks	4480
lime & shale	4500
lime	4545
lime w/chert	4605
chalky lime w/chert	4680
chalky lime	4863
lime & shale	4988
lime	5132
lime & shale	5225
lime	5520
lime w/chert	5564
lime	5575
shale & sand	5609
sand	5627
shale & sand	5670
lime & shale	5730
Total Depth	

TOPS: SCOUT

Heebner	4362
Lansing	4515
Marmaton	5132
Cherokee	5284
Morrow Sand	5576
Mississippi	5666

SINCLAIR OIL & GAS COMPANY

P. O. Box 466
Chase, Kansas
August 3, 1960

State Corporation Commission
State of Kansas
211 North Broadway
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 5 1960

CONSERVATION DIVISION
Wichita, Kansas

Gentlemen:

This is to advise that the following gas well has been completed;

OPERATOR: Sinclair Oil & Gas Company

LEASE: Mamie E. Angell

WELL NO: 2

LOCATION: 1980' from the East line and 660' from the South line of the NE 1/4
of Section 30-32S-29W, Meade County, Kansas

PURCHASER: Not connected to sales line

FIELD: Angell Pool

PRODUCING FORMATION: Morrow Sand

TOP OF PRODUCING FORMATION: 5570'

PRODUCING FORMATION: 5570' to 5621'

TOTAL DEPTH: 5730'

PLUGGED BACK TOTAL DEPTH: 5686'

ACIDIZED: Morrow sand from 5570' to 5621' thru perforations in 4 1/2" casing with 500
gallons mud acid and Acid Petro-Fraced same with 25000 Gallons jelled acid
and 25000# sand. 7-28-60

PRODUCTION TEST: 8-1-60

How produced - Flow

Oil Produced - 10 bbls. condensate while on test

Gas Produced - 4,672 MCF thru 3/4" choke

Length of test - 24 hours.

Yours very truly,

C.B. York.

CBY/r