

15-119-21013

32-32s-29w

TRILOBITE TESTING L.L.C.

ORIGINAL

OPERATOR : Sublette Oil Co.

DATE 12-10-99

WELL NAME: Rexford #1-32

KB 0.00 ft

TICKET NO: 12248 DST #1

LOCATION : 32-32s-29w Meade co KS

GR 0.00 ft

FORMATION: Marmaton

INTERVAL : 5260.00 To 5310.00 ft

TD 5310.00 ft

TEST TYPE: CONVENTIONAL

RECORDER DATA

Mins	Field	1	2	3	4	TIME DATA-----
PF 30 Rec.	11019	11019	3026			PF Fr. 1414 to 1444 hr
SI 45 Range(Psi)	4500.0	4500.0	4995.0	0.0	0.0	IS Fr. 1444 to 1529 hr
SF 60 Clock(hrs)	12hr	12hr	elect			SF Fr. 1529 to 1629 hr
FS 60 Depth(ft)	5310.0	5310.0	5267.0	0.0	0.0	FS Fr. 1629 to 1729 hr

	Field	1	2	3	4	
A. Init Hydro	2488.0	2475.0	2503.0	0.0	0.0	T STARTED 1130 hr
B. First Flow	56.0	56.0	26.0	0.0	0.0	T ON BOTM 1413 hr
B1. Final Flow	158.0	174.0	194.0	0.0	0.0	T OPEN 1414 hr
C. Ir Shut-in	1694.0	1679.0	1690.0	0.0	0.0	T PULLED 1729 hr
D. Init Flow	203.0	224.0	196.0	0.0	0.0	T OUT 2000 hr
E. Final Flow	350.0	395.0	348.0	0.0	0.0	
F. Fl Shut-in	1660.0	1660.0	1663.0	0.0	0.0	
G. Final Hydro	2454.0	2422.0	2410.0	0.0	0.0	
Inside/Outside	O	O	I			

TOOL DATA-----	
Tool Wt.	1800.00 lbs
Wt Set On Packer	24000.00 lbs
Wt Pulled Loose	95000.00 lbs
Initial Str Wt	78000.00 lbs
Unseated Str Wt	80000.00 lbs
Bot Choke	0.78 in
Hole Size	7.78 in
D Col. ID	2.25 in
D. Pipe ID	3.38 in
D.C. Length	232.00 ft
D.P. Length	5026.00 ft

RECOVERY

Total Fluid 500.00 ft of 232.00 ft in DC and 268.00 ft in DP
 120.00 ft of Mud
 0.00 ft of 100% mud
 80.00 ft of Gas cut watery mud
 5.00 ft of 2% gas 20% water 88% mud
 200.00 ft of Muddy water
 1.00 ft of 95% water 5% mud
 1.00 ft of
 0.00 ft of

SALINITY 70000.00 P.P.M. A.P.I. Gravity 0.00

BLOW DESCRIPTION

Initial Open:

Weak blow built to bottom of bucket in 28 minutes.

Initial Shut-In:

No blow back.

Final Flow:

Weak blow built to bottom of bucket in 38 minutes

Final Shut-In:

No blow back

SAMPLES:

SENT TO:

RECEIVED

KANSAS CORPORATION COMMISSION

FEB 24 2000

CONSERVATION DIVISION
WICHITA, KS

MUD DATA-----

Mud Type	chemical
Weight	9.10 lb/cf
Vis.	46.00 S/L
W.L.	8.00 in3
F.C.	0.00 in
Mud Drop	

Amt. of fill	0.00 ft
Btm. H. Temp.	130.00 F
Hole Condition	good
% Porosity	0.00
Packer Size	6.75 in
No. of Packers	2
Cushion Amt.	0.00
Cushion Type	
Reversed Out N	
Tool Chased N	

Tester	Scott Bugbee
Co. Rep.	Paul
Contr.	Abercrombie
Rig #	4
Unit #	
Pump T.	

Test Successful: Y

*** TOOL DIAGRAM *** CONVENTIONAL

ORIGINAL

WELL NAME: Rexford #1-32

LOCATION : 32-32s-29w Meade co KS

TICKET No. 12248 D.S.T. No. 1 DATE 12-10-99

TOTAL TOOL TO BOTTOM OF TOP PACKERS 27

INTERVAL TOOL

BOTTOM PACKERS AND ANCHOR 19

TOTAL TOOL 46

DRILL COLLAR ANCHOR IN INTERVAL

D.C. ANCHOR STND.Stands Single Total

D.P. ANCHOR STND.Stands Single 1 Total 31

TOTAL ASSEMBLY 77

D.C. ABOVE TOOLS.Stands4 Single Total 232

D.P. ABOVE TOOLS.Stands81 Single 1 Total 5026

TOTAL DRILL COLLARS DRILL PIPE & TOOLS .. 5335

TOTAL DEPTH 5310

TOTAL DRILL PIPE ABOVE K.B. 25

REMARKS:

W .14 at 50 deg

0000 chlorides

P.O. SUB top of tool	5233
C.O. SUB 1' DP	5234
S.I. TOOL 5'	5239
HMV 5'	5244
JARS 5'	5249
SAFETY JOINT 2'	5251
PACKER 5'	5256
PACKER	5260
DEPTH 5260	5261
1'	5262
ANCHOR	5267
1' perfr	5262
Alpine Rec.	5267
5' PU sub	5267
5' perf	5272
1' c/o sub	5273
31' pipe	5304
1' c/o sub	5305
Akl Rec.	5310
BULLNOSE	5310
T.D. 5'	5310

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 24 2000

CONSERVATION DIVISION
WICHITA, KS

ORIGINAL

TEST HISTORY

12248 DST#1 Rexford #1-32 Sublette Oil Co.

RECEIVED

KANSAS CORPORATION COMMISSION


FEB 24 2000

CONSERVATION DIVISION
WICHITA, KS

Flag Points

t (Min.) PK PSig

A:	0.00	2503.01
B:	0.00	26.46
C:	31.17	194.19
D:	43.83	1698.74
E:	0.00	196.55
F:	58.58	348.34
G:	61.00	1683.07
H:	0.00	2418.94



ORIGINAL

TRILOBITE TESTING L.L.C.

PERATOR : Sublette Oil Co.

DATE 12-12-99

ELL NAME: Rexford 1-32

KB 27040.00 ft

TICKET NO: 12249

DST #2

LOCATION : 32-32s-29w Meade co KS

GR 2699.00 ft

FORMATION: Morrow

INTERVAL : 5626.00 To 5693.00 ft

TD 5693.00 ft

TEST TYPE: CONVENTIONAL

REORDER DATA

mins		Field	1	2	3	4	TIME DATA-----
30	Rec.	11019	11019	3026			PF Fr. 1032 to 1102 hr
45	Range (Psi)	4500.0	4500.0	4995.0	0.0	0.0	IS Fr. 1102 to 1147 hr
60	Clock (hrs)	12hr	12hr	elect			SF Fr. 1147 to 1247 hr
90	Depth (ft)	5693.0	5693.0	5633.0	0.0	0.0	FS Fr. 1247 to 1417 hr

	Field	1	2	3	4	
Init Hydro	2837.0	0.0	2720.0	0.0	0.0	T STARTED 0800 hr
First Flow	203.0	0.0	106.0	0.0	0.0	T ON BOTM 1031 hr
Final Flow	248.0	0.0	230.0	0.0	0.0	T OPEN 1032 hr
In Shut-in	1027.0	0.0	988.0	0.0	0.0	T PULLED 1417 hr
Init Flow	282.0	0.0	212.0	0.0	0.0	T OUT 1700 hr
Final Flow	0.0	0.0	245.0	0.0	0.0	
Fl Shut-in	0.0	0.0	983.0	0.0	0.0	TOOL DATA-----
Final Hydro	2781.0	0.0	2706.0	0.0	0.0	Tool Wt. 1800.00 lbs
side/Outside	0	0	I			Wt Set On Packer 26000.00 lbs
						Wt Pulled Loose 110000.00 lbs
						Initial Str Wt 83000.00 lbs
						Unseated Str Wt 84000.00 lbs
						Bot Choke 0.78 in
						Hole Size 7.78 in
						D Col. ID 2.25 in
						D. Pipe ID 3.38 in
						D.C. Length 232.00 ft
						D.P. Length 5397.00 ft

COVERY

t Fluid 235.00 ft of 232.00 ft in DC and 3.00 ft in DP
 5.00 ft of Slightly gas cut mud
 10 ft of 2% gas 98% mud
 10 ft of
 10 ft of
 10 ft of
 10 ft of
 10 ft of
 10 ft of

INITY 0.00 P.P.M. A.P.I. Gravity 0.00

W DESCRIPTION

tial Flow:
 Strong Blow. Bottom of bucket in 45
 seconds. Gas to surface in 7 minutes
 Gas will burn.

tial Shut-In:
 Bled 2". No blow back.
 al Flow:
 Bottom of bucket as soon astool open
 al Shut-In:
 3led 2". No blow back

PLES: yes
 TO: Caraway Analytical

Test Successful: Y

RECEIVED
 KANSAS CORPORATION COMMISSION

FEB 24 2000

CONSERVATION DIVISION
 WICHITA, KS

MUD DATA-----
 Mud Type Chemical
 Weight 9.10 lb/cf
 Vis. 44.00 S/L
 W.L. 8.00 in3
 F.C. 0.00 in
 Mud Drop

Amt. of fill 0.00 ft
 Btm. H. Temp. 130.00 F
 Hole Condition good
 % Porosity 0.00
 Packer Size 6.75 in
 No. of Packers 2
 Cushion Amt. 0.00
 Cushion Type
 Reversed Out N
 Tool Chased N
 Tester Scott Bugbee
 Co. Rep. Paul Gunzelman
 Contr. Abercrombie
 Rig # 4
 Unit #
 Pump T.